


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-077-10110- WELL PLUGGING RECORD
0000

NORTH



Locate well correctly on above
Section Plat

Harper

County. Sec. 27 Twp. 31 Rge. (E)9 (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE

Lease Owner Earl F. Wakefield & Etal.

Lease Name Robinson Well No. 1

Office Address 515 Union Center Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas & Oil Well

Date well completed 4/14/55 19

Application for plugging filed 10/28/57 19

Application for plugging approved 10/29/57 19

Plugging commenced 10/31/57 19

Plugging completed 11/9/57 19

Reason for abandonment of well or producing formation Not economical

If a producing well is abandoned, date of last production March 1957

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives

Producing formation Mississippi Depth to top 3999 Bottom 4420 Total Depth of Well 4420 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8/ 5/8"	248'	None
				5 1/2"	4418'	3200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole 4420 to 4390 with 5 sacks cement;
4390 to 210 with 65 sacks drilling mud; 210 to 150
with crushed rock & cement 80 sacks; 150 to 40'
with clay; 40 to 0 with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield

Address 515 Union Center Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Earl F. Wakefield (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 1957

E. A. Snow
Notary Public.

My commission expires July 26, 1958

PLUGGING
FILE SEC 27 T 31 R 96
BOOK PAGE 57 LINE 31

15-077-10110-0000

Robinson #1
Owners: Earl F. Wakefield
and others
Contractor: Earl F. Wakefield
Comm: 4/1/55 Comp: 4/14/55

NE SE SE
27-31-9W
Harper Co., Kansas
Casing 248' of 8 5/8"
4418' of 5 1/2"

Elevation 1622

Surface	248
Red Bed	840
Shale & Shells	1525
Lime	1875
Lime & Shale	2145
Shale & Shells	2335
Shale	2950
Shale & Shells	3055
Shale	3244
Shale & Shells	3360
Shale & Lime	3460
Shale & Shells	3545
Shale	3602
Sand	3694
Top Kans. City 3694	
Shale & Lime	3715
Shale & Shells	3784
Lime	3917
Shale & Shells	4000
Lime	4102
Lime & Shale	4148
Lime	4176
Shale & Lime	4292
Shale & Shells	3999
Mississippi Chat	4420
Total Rotary Depth	4420

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby agree and certify that the above is a true and correct copy of the log on the Robinson #1 well located NE SE SE, 27-31-9W, Harper County, Kansas.

Earl F. Wakefield

Sworn and subscribed before me this 23rd day of April, 1955.

[Signature]

Notary Public

My commission expires July 26, 1958.

OCT 29 1957
RECEIVED
DIVISION

PLUGGING
FILE SEC. 27 T. 31 R. 9W
BOOK PAGE 57 LINE 31