


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

15-077-10130000



Locate well correctly on above
Section Plat

Harper County, Sec 34 Twp 31 Rge. 9 (E) (W)
Location as "NE/CNW&SW" or footage from lines NE SE
Lease Owner Raymond Oil Company
Lease Name Dusenbury Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19__
Application for plugging filed 19__
Application for plugging approved 19__
Plugging commenced 8/8/68 19__
Plugging completed 8/12/68 19__
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4436 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	none
				5 1/2"	4436'	3205'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Checked hole, sanded back to 3945' and ran 5 sacks of cement.
Couldn't get connection off casing and head in cellar.
Removed braden head and put on stripper head. Worked pipe
at no gain in tension. Shot pipe at 3283', 3190', worked
pipe loose and pulled 101 joints. Set 10' rock bridge at 210'
and ran 25 sacks of cement. Mudded hole to 40', 10' rock
bridge and ran 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 15th day of AUGUST, 1968.
Margaret Melcher
Notary Public.
My commission expires February 15, 1971

15-077-10113-0000

Carter-Dusenbury #1
Owner: Carter Oil Co. & Et al
Contractor: Earl F. Wakefield
Comm: 7/17/56 Comp: 8/6/56

C - Ne - SE
34 - 31S- 9W
Harper County, Kansas
Casing 8 5/8" Set @ 230'
5 1/2" Set @ 4475'

Elevation 1592 D F

Surface	232
Shale & Shells	785
Shale	1375
Lime & Shale	2976
Lime	3040
Lime & Shale	3616
Lime	3631
Sand	3670
Shale & Lime	3862
Lime	3885
Shale & Sandy Shale	3935
Shale & Lime	3952
Shale	3960
Lime & Shale	4035
Lime	4174
Lime & Shale	4292
Lime	4345
Shale & Lime	4389
Chert (Mississippi)	4410
Lime	4427
Chat	4475
T. R. D.	4475

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1968
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log of the Carter-Dusenbury #1 well located C NE SE 34-31S-9W, Harper County, Kansas

Earl F. Wakefield

Subscribed and sworn to before me this 14 day of August, 1956

[Signature]

My Commission Expires: 7-26-58