


15-077-30(71-0000)

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Harper County, Sec. 34 Twp. 31 Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Earl F. Wakefield
Lease Name Dusenbury Well No. 2
Office Address 515 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed November 3, 1954
Application for plugging filed October 27 1957
Application for plugging approved October 29 1957
Plugging commenced October 20 1957
Plugging completed October 30 1957
Reason for abandonment of well or producing formation Not Eco.

If a producing well is abandoned, date of last production April 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Mississippi Depth to top 4422 Bottom 4463 Total Depth of Well 4463 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	223'	None
				5 1/2"	4463'	3267'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with 30 sacks Aquajel to 220'
Set Bridge, filled to 195' with rock,
Put in 20 sacks cement to 140', filled
with clay, 10 sacks cement to top

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1957
11-14-57
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Earl F. Wakefield
Address 515 Union Center Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Earl F. Wakefield (Employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of November, 1957

C. A. Snow
Notary Public.

My commission expires July 26, 1958

PLUGGING
FILE SEC 34T 31 R 9W
BOOK PAGE 57 LINE 33

15-077-3071-0000

Dusenbury #2
Owner: Earl F. Wakefield and et al
Contractor: Earl F. Wakefield
Comm: 10/7/54 Comp: 10/24/54

NE NE NW
34-31-9W
Harper County, Kansas
Casing: 223" of 8 5/8"
4463" of 5 1/2"

Elevation 1615 R.B.

Surface	223
Red Bed and Shale	850
Shale and Shells	1477
Lime and Shale	1845
Shale, Shells and Lime	1945
Lime and Shale	2325
Shale and Shells	2520
Sandy Shale	2682
Shale and Shells	2830
Lime and Shale	3450
Lime	3520
Lime and Shale	3617
Sand and Shale	3670
Lime	3699
Sandy Lime and Shale	3765
Lime	3830
Lime and Shale	3875
Lime	3970
Shale and Lime	4164
Lime	4210
Lime and Shale	4407
Shale and Lime Streaks	4422
Mississippi Lime	4463
Total Rotary Depth	4463

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby agree and certify that the above is a true and correct copy of the log on the Dusenbury #2 well located NE NE NW, 34-31-9W, Harper County, Kansas.

Earl F. Wakefield

Sworn and subscribed before me this 29th day of October, 1954.

[Signature]

Notary Public

My commission expires July 26, 1958.

OCT 29 1954
DIVISION
Kansas

PLUGGING
FILE SEC. 34 T. 31 R. 9W
BOOK PAGE 57 LINE 33