


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sumner County. Sec. 1 Twp. 30S Rge. 1 ~~XX~~ (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Pack Oil Co.
Lease Name Hurst Well No. 1
Office Address 550 4th Nat'l. Bank Bldg. - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed January 18, 1960
Application for plugging filed January 18, 1960
Application for plugging approved January 18, 1960
Plugging commenced January 18, 1960
Plugging completed January 18, 1960
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3849 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	335'	None
				13	90'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud to 200 feet. Plug at 200 feet with 15 sacks cement on plug. Hole filled with heavy rotary mud to 35 feet. Plug at 35 feet with 10 sacks cement on plug. Rat hole filled with heavy rotary mud and capped with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc. - License #209
Address _____

STATE OF Kansas, COUNTY OF Butler, ss.
Dale R. Daniel, employee of Contractor (employee of owner or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale R. Daniel
Box 448 - El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January, 1960

My commission expires May 21, 1960 Ernest Siffard Notary Public.



Casing Record

13 3/8" 90' Cemented
w/350 sacks

8 5/8" 335' Cemented
w/200 sacks

T.D. 3849'

Look in East

R

Location: NW NW NE
Section: 1-30S-1W
Summer County, Kansas
Farm: Hurst #1
Well Owner: Pack Oil Co.
Contractor: White & Ellis Drig., Inc.
Started: 1/2/60
Completed: 1/18/60

Kelly Bushing Measurement 5' above ground level.

FORMATION	DEPTH
Soil	0-10
Clay	20
Sand	85
Shale	230
Antihydrate	245
Antihydrate & Shale	530
Shale & Shells	575
Lime & Shale	950
Shale	990
Lime & Shale stks.	1120
Shale & Lime stks.	1205
Shale & Shells	1285
Shale & Lime stks.	1490
Lime & Shale	1750
Shale	1780
Shale & Lime Shells	1870
Shale & Shells	1910
Lime & Shale stks.	2060
Lime & Shale	2130
Shale & Lime shells	2280
Shale & Shells	2385
Shale	2457
Sand	2522
Shale	2635
Lime & Shale	2735
Shale & Shells	2794
Lime	3024
Lime & Shale	3082
Shale & Shells	3130
Lime & Shale	3237
Shale & Shells	3325
Lime & Shale	3389
Lime	3644
Lime, chert	3663
Lime	3772
Shale	3832
Sand	3849

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1961
CONSERVATION DIVISION
Wichita, Kansas

	TOPS
Stalnaker	2457
Kansas City	2794
Mississippi	3389
Kinderhook	3772
Simpson	3832

D. & A.