

15-191-00089-00-00

P

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sumner County. Sec. 1 Twp. 30 Rge. 1 W (E) (W)
Location as "NE/CNW/SW" or footage from lines. NE NE NW
Lease Owner Mull Drilling Co. Inc
Lease Name Kerley Well No. 1
Office Address 670 N. 4th. Natl Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 12-5-59 19
Application for plugging filed 11-22-61 19
Application for plugging approved 11-22-61 19
Plugging commenced 8:00 A. M. 11-22-61 19
Plugging completed 4:00 P. M. 11-28-61 19
Reason for abandonment of well or producing formation _____
Non Productive.
If a producing well is abandoned, date of last production 11-18-61 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH.

	X		

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gene Graham
Producing formation Simp. Depth to top _____ Bottom _____ Total Depth of Well 8835' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pipe shot off at 2857' 4 sacks cement at 3830'. Mud to 240' 10' rock bridge, dumped 15 sax cement. Mud to 25', 10' rock bridge. Dumped 5 sax cement on bridge completing plugging.

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wilson Inc.
Address Stafford, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts Prod Dept.
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 19 61

Betts H. Salter

My commission expires October 16, 1965

Notary Public.



15-191-00089-0000

ROTARY DRILLING LOG

OPERATOR: Mull Drilling Company, Inc.
KERLEY NO. 1
NE NE NW Section 1-30-1W,
Sumner County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
CON: 11-9-59
COMP: 11-30-59

Formations:

Remarks: Set 8-5/8" surface casing
at 325' cemented with 250
sacks cement

Surface Soil - Sand	39'
Soil & Lime	170'
Shale & Lime	220'
Lime & Shale	292'
Lime	325'
Lime & Shale	1120'
Shale & Lime	1300'
Shale & Lime Streaks	1470'
Lime	1625'
Shale & Lime	1919'
Lime & Shale	2432'
Shale & Lime	2460'
Sand	2517'
Shale	2620'
Shale & Lime	2730'
Lime & Shale	2840'
Lime	2995'
Lime & Shale	3392'
Lime	3491'
Lime w/Chert Streaks	3525'
Lime	3752'
Shale & Lime	3808'
Shale	3828'
Sand	3839'
Rotary Total Depth	3839'

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1961
CONSERVATION DIVISION
Wichita, Kansas

Set 4-1/2" casing at 3839' cemented
with 125 sacks Pozmix.

We certify the above log is true and
correct to the best of our knowledge
and belief.

CAPITT DRILLING, INC.

R. R. McNicol