


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sumner

County. Sec. 3 Twp. 30s Rge. 1W (E) (W)

Location as "NE/CNWKSWK" or footage from lines. 6/NE SE

Lease Owner Jimmie Razook

Lease Name Schmeissner Well No. 1

Office Address 2101 E. 21 st. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-16-69 19

Application for plugging filed 11-16-69 19

Application for plugging approved 11-16-69 19

Plugging commenced 11-16-69 19

Plugging completed 11-16-69 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Howard Hess

Producing formation Depth to top Bottom Total Depth of Well 3455 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug at 260 ,run 30 sx. of wet cement through drill pipe,
Plug at 40' and 1/2 sx hulls, and 8 sx. of cement, 2 sx.
in rat-hole.

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Triangle Drilling Co.

Address 324 N. Orchard, Eldorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

Harry Hughes (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry Hughes

(Address)

SUBSCRIBED AND SWORN to before me this 18 day of November, 1969

My commission expires Nov. 12 1972 Notary Public.



TRIANGLE DRILLING

324 North Orchard
EL DORADO, KANSAS

15-191-20159-00-00 ^{PR}

To Jimmie Razook

Invoice No. _____

2101 E. 21st.

Date November 18, 1969

Wichita, Kansas

For Month Of _____

Lease Schmeissner 1/4 NE SE 3-30S-1W Sumner County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1969
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

0	-----	30	Sand and Soil
30	-----	45	Shale
45	-----	235	Shale and Lime Shells
235	-----	260	Lime and Shale
260	-----	510	Lime and Shale
510	-----	728	Shale and Lime Shells
728	-----	880	Shale and Lime Stks.
880	-----	1060	Lime and Shale
1060	-----	1320	Shale and Lime
1320	-----	1510	Shale and Lime Stks.
1510	-----	1695	Shale and Lime
1695	-----	1750	Shale and Lime
1750	-----	1775	Lime and Shale
1775	-----	1883	Shale and Lime
1883	-----	2060	Shale and Lime
2060	-----	2131	Lime and Shale
2131	-----	2194	Shale and Lime
2194	-----	2256	Shale and Lime
2256	-----	2340	Shale and Lime Shells
2340	-----	2484	Shale and Lime
2484	-----	2510	Sand
2510	-----	2595	Sand and Shale
2595	-----	2665	Sand
2665	-----	2825	Lime and Shale
2825	-----	2840	Lime KC
2840	-----	2937	Lime KC
2937	-----	3010	Lime
3010	-----	3095	Lime KC
3095	-----	3165	Lime
3165	-----	3215	Lime
3215	-----	3295	Lime and Shale
3295	-----	3377	Shale
3377	-----	3432	Lime and Shale
3432	-----	3455	Miss. R.T. D.