

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-191-00714-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sumner County. Sec. 4 Twp. 30 Rge. 1 (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner Franco Central Oil Company
Lease Name Roy Well No. 1
Office Address 4th National Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed December 18, 19 58
Application for plugging filed December 18 19 58
Application for plugging approved December 18 19 58
Plugging commenced December 18 19 58
Plugging completed December 18 19 58
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham
Producing formation Depth to top Bottom Total Depth of Well 3903 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	340'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy rotary mud to
340 ft. Wooden plug at 340 ft. with
15 sacks cement on plug. Hole filled
with heavy rotary mud to 35 ft. Wooden
plug at 35 ft. with 10 sacks cement on
plug.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor White & Ellis Drilling, Inc. - License #209
Address Box 448 El Dorado, Kansas

STATE OF Kansas COUNTY OF Butler, ss.
Dale R. Daniel (Employee of Contractor) (employee of owner) (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale R. Daniel
Box 448 El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of December, 19 58
My commission expires May 21, 1960
Notary Public.

PLUGGING
FILE SEC. 4 T. 30 R. 1W
BOOK PAGE 7 LINE 10

Casing Record
8 5/8

15-191-00714-00-00

340⁺ cemented
W/225 sacks

Location: NE SW SW sec. 4-30S-1W
Sumner County, Kansas
Farm: Roy #1
Well Owner: Franco Central Oil Co.
Contractor: White & Ellis Drilling, Inc.
Started: 11-30-58
Completed: 12-18-58

T. D. Kelly Bushing 5⁺ above ground level:

FORMATION	DEPTH
Soil	0-10
Sandy Shale	75
Shale & anhydrite	274
Lime anhydrite	280
Shale & Anhydrite	335
Lime anhydrite	340
Shale & anhydrite	445
Shale W/Lime stks.	490
Shale & Lime	585
Red Rock	605
Lime & Shale	1005
Sticky Shale & Lime stks	1280
Shale & Shell	1370
Shale, sticky	1635
Lime & Shale stks.	1800
Shale & Lime	1860
Lime	1985
Shale	2025
Lime & Shale	2220
Shale & Lime stks.	2275
Shale & Lime	2435
Shale, sticky	2535
Lime	2538
Sand N.S.O.	2693
Shale & Lime	2800
Shale	2880
Lime, Kansas City	3074
Shale & Lime stks	3130
Lime & Shale	3335
Shale & Lime	3418
Lime	3429
Shale	3439
Lime, Mississippi	3756
Shale	3792
Sand, Simpson Show oil	3798
Sand	3880
Sand & Shale	3891
Lime, Arbuckle	3903

Figures indicate bottom of formation

Dry Hole
Plugged & Abandoned

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE SEC.	4 T.36 R.1W
BOOK PAGE	7 LINE 10.