STATE OF KANSAS
STATE CORPORATION COMMISSION


15-191-00437-00-00

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sumner County. Sec. 4 Twp. 30S Rge. ____ (E) 1 (W)

Location as "NE/CNW¼SW¼" or footage from lines SW NE NE

Lease Owner George P. Vye

Lease Name Edens Well No. 1

Office Address 1006 Central Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 12/9/57 19

Application for plugging filed 10/6/58 19

Application for plugging approved 10/6/58 19

Plugging commenced 10/14/58 19

Plugging completed 10/16/58 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well F. L. Hagar

Producing formation ____ Depth to top ____ Bottom ____ Total Depth of Well 3807' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	352'	none
				5-1/2"	3800'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ____ feet to ____ feet for each plug set.

Fill with sand to 3805' and 5 sacks of cement. Mud to 200'. 10' rock bridge and 20 sacks cement. Mud to 20', 5' rock bridge and 5 sacks cement, cut off surface to below plow depth and weld on cap.

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Box 506 Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jack H. Douglass (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack H. Douglass

423 Union National Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 62

Ruth G. Lawrence
Notary Public.

My commission expires June 15, 1963

15-191-00437-00-00

ROTARY DRILLING LOG

OPERATOR: George P. Vye
Approx. SW NE NE Sec. 4-29S-1W,
Sumner County, Kansas
EDENS NO. 1

CONTRACTOR: Capitt Drilling, Inc.
COMM: 11/24/57
COMP: 12/9/57

Remarks: Set 8-5/8" surface casing at 352' cemented with 250 sacks common, later adding 75 sacks cement around top, 3% C.C.

Formations:

Shale - Sand	30'
Shale	125'
Lime & Shale	595'
Lime	780'
Shale	795'
Lime w/Shale breaks	975'
Shale	1010'
Shale & Lime	1195'
Shale & Shells	1787'
Lime & Shale	2000'
Shale & Shells	2105'
Lime & Shale	2330'
Shale	2518'
Sand	2690'
Shale	2735'
Shale & Lime Shells	2820'
Shale & Lime	2854'
Lime	3060'
Shale & Lime	3195'
Lime	3229'
Shale & Lime	3421'
Lime	3752'
Shale	3774'
Core #1	3789'
Shale	3791'
Core #3	3804'
Sand	3807'
Rotary Total Depth	3807'

Set 5-1/2" oil string at 3800' cemented with 100 sacks Pozmix.

We certify the above log is true and correct to the best of our knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1958
CONSERVATION DIVISION

PLUGGING
FILE SEC 4 T 29 R 1W
BOOK PAGE 134 LINE 1