

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-20823-0000  
LEASE NAME McGuire

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1  
Ft. from S Section Line \_\_\_\_\_  
Ft. from E Section Line \_\_\_\_\_

LEASE OPERATOR PRATT WELL SERVICE, INC.  
ADDRESS P.O. BOX 847 PRATT, KS 67124  
PHONE (316) 672-2531 OPERATORS LICENSE NO. 5893

SEC. 18 TWP. 28S RGE. 13W(E) or (W)  
COUNTY PRATT  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 7-12-00  
Plugging Completed 8-19-00

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JULY 12, 2000 (date)  
by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? DO NOT HAVE ONE

Producing Formation \_\_\_\_\_ Depth to Top 2902 Bottom 4402 T.O. 4725'  
P.B.T.D. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	surface			8 5/8"	@214'	
	production			5 1/2"		33 Jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each so Log-Tech on location and shot casing @ 1509' (free) and set 5 1/2" bot bridge plug @ 4035', then dumped 2 sks cement on top. Acid Services on location - 1st plug @ 860' w/ 50 sks cement, pumped 8 sks gel H2O, 50 sks cement & 2 sks gel H2O. 2nd plug @ 242' w/ 50 sks cement. Break circu and pumped 50 sks cement and 1 bbl H2O. 3rd plug @ 40' w/ 10 sks cement, break circu and circulate cement to surface. Cement to top of surface pipe, 11' below ground level. Total of 110 sks 60/40 poz and 1376 lbs cement gel.

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. CP-8910N CONSERVATION COMMISSION  
Address P.O. BOX 847 PRATT, KS 67124 SEP 06 2000

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PRATT WELL SERVICE, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

CONSERVATION DIVISION  
Wichita, Kansas

Amy Robertson, Production Clerk (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed in  
the same are true and correct, so help me God.

(Signature) Amy Robertson  
(Address) P.O. Box 847 Pratt, KS 67124



SUBSCRIBED AND SWORN TO before me this 30 day of August, 2000  
Kevin C. Gates  
Notary Public

My Commission Expires: 3/13/04

