

15-151-20738-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER APRIL 28- MAY 5, 1980

LEASE NAME EUBANK

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

C NE NE

SEC. 19 TWP. 28 RGE. 13 W

COUNTY PRATT

Date Well Completed MAY 5, 1980

Plugging Commenced JAN 5, 1994

Plugging Completed JAN. 7, 1994

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PRATT WELL SERVICE, INC.

ADDRESS P O BOX 847 PRATT, KS. 67124

PHONE#(310) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JAN. 10, 1994 (date)

by DUANE RANKIN (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3200

Show depth and thickness of all water, oil and gas formations. PERFS: 2905-15

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	256	8 5/8	256	0
		0	3091	4 1/2	3091	48JTS. 2030 FT.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
SANDED BACK TO 2780 FT, DUMPED 4 SX CEMENT ON TOP. SHOT OFF CASING AT 2660 FT., DID NOT COME LOOSE, SHOT AGAIN AT 2030, CAME LOOSE. TOP HOLE PLUGGED THE WELL WITH 400# HULLS, 20 SX GEL, 200 SX CEMENT, 60-40-POZ., 6% GEL. RIGGED DOWN AND MOVED OFF.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KS. 67124

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1994

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PRATT WELL SERVICE, INC.

STATE OF KANSAS COUNTY OF PRATT


JUDY BERRY

(Employee of PRATT WELL SERVICE, INC.)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO PWS, Inc.



SUBSCRIBED AND SWORN TO before me this 25th day of January, 1994

Dorothy M. Ferguson
Notary Public

My Commission Expires Feb. 6, 1997