

SEP 26 1978

STATE OF KANSAS STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

CONSERVATION DIVISION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to Conservation Division State Corporation Comm. 245 North Water Wichita, KS 67202

Pratt County, Sec. 20 Twp. 28S Rge. 13 E/W Location as "NE/CNW 1/4 SW 1/4" or footage from lines C SW 1/4 NE 1/4 NE 1/4

Lease Owner Petrie Enterprises, Inc. Lease Name Letholt Well No. 1

Office Address R. R. 1 Pratt, Kansas 67124 Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole


Date Well completed September 11 1978 Application for plugging filed September 11 1978 Application for plugging approved September 11 1978 Plugging commenced September 11 1978 Plugging completed September 11 1978 Reason for abandonment of well or producing formation

Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen Producing formation Depth to top Bottom Total Depth of Well Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

plugged: With 50 sacks @ 540' With 40 sacks @ 210' With 20 sacks @ 40' Plugged by HOWCO Completed at 6:00 PM

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert & Jones 830 Sutton Place Wichita, Kansas

STATE OF COUNTY OF

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanley D. Petrucci 13131 Pratt Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September 1978

Notary Public

My commission expires



GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

RECEIVED  
STATE OF KANSAS COMMISSION

SEP 26 1978

CONSERVATION DIVISION  
WICHITA, KANSAS

Letholt #1  
NE/4 Sec 20-283-13W  
Pratt County Kansas

Commenced: 9-4-78

Completed: 9-11-78

OPERATOR: PETRIE EXPLORATION CO., INC.

Depth		Formation	Remarks
From	to		
0	190	Sand-Clay	Ran 6 jts of 43# 12 3/4" csg set @ 218' Cemented w/ 275 sbs 60/40 Pozmix 2% Gel 3% CC PD @ 8:45 p.m. 9-4-78
190	225	Redbed	
225	475	Redbed-Shale	
475	1700	Shale-Shells	
1700	1990	Shale	
1990	2125	Shale-Lime	
2125	2305	Lime-Shale	DRY & ABANDONED
2305	2480	Shale	
2480	2990	Lime-Shale	
2990	3170	Lime	
	3170 - TD		

STATE OF KANSAS )  
                          ) SS  
County of SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above  
Drillers' Well Log is true and correct to the best of my knowledge and belief and  
according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
JAMES S. SUTTON II

Subscribed and sworn to before me this 15th day of September, 1978.

*Elizabeth J. Edwards*  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

