

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-151-20831-0000

LEASE NAME Healy

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4620 Ft. from (S) Section Line

4620 Ft. from (E) Section Line

SEC. 20 TWP. 28 RGE. 13 (E) or (W)

COUNTY Pratt

LEASE OPERATOR Knighton Oil Company, Inc.

ADDRESS 221 S. Broadway, Suite 710

PHONE (316) 264-7918 OPERATORS LICENSE NO. 5010

Date Well Completed 12/17/80

Character of Well Gas

Plugging Commenced 10/9/00

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Plugging Completed 10/9/00

The plugging proposal was approved on August 23, 2000 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? yes

Producing Formation Indian Cave Depth to Top 2892 Bottom 2902 T.O. 3242

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	254	8 5/8"	254	None	
	Production Pipe	3231	4 1/2"	1980		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
First plug at 800' w/50sxs cement (60/40 poz, 6% gel)  
Second plug at 271' w/50sxs cement (60/40 poz, 6% gel)  
Third plug at 40' w/10sxs cement (60/40 poz, 6% gel)

Name of Plugging Contractor Pratt Well Surface License No. 5893

Address P.O. Box 847 Pratt, KS 67214

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Earl M. Knighton, Jr.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Earl M. Knighton, Jr.

221 S. Broadway, #710

(Address) Wichita, KS 67202

OCT 16 2000

CONSERVATION DIVISION WICHITA, KS SUBSCRIBED AND SWORN TO before me this 16th day of October, 2000

My Commission Expires: 9/30/03

Notary Public David D. Montague

DAVID D. MONTAGUE  
Notary Public - State of Kansas  
My Appt. Expires 9-30-03

Form 27-  
Revised 05-01

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to Cons. Div. office within 30 days.

660 Ft. from S(N) Line of Section (circle one)  
660 Ft. from E(W) Line of Section (circle one)

LEASE OPERATOR Knighton Oil Co., Inc.  
 ADDRESS 221 S. Broadway Suite 710  
 CITY, STATE, ZIP Wichita, Kansas 67202  
 PHONE# 316,264-7918 OPERATORS LICENSE NO. 5010  
 Character of Well Gas  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION C - NW - NW  
 SEC. 20 TWP. 28 S. RGE 13 (E) or (W)  
 COUNTY Pratt  
 Date Well Completed \_\_\_\_\_  
 Date Plugging Commenced October 9, 2000  
 Date Plugging Completed October 9, 2000

The plugging proposal was approved on September 25, 2000 (date)  
 by Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation(s) Coal 2892 to 2895 & 2898 Depth to Top \_\_\_\_\_ Bottom 1870-3214 T.D. 3242

Show depth and thickness of all water, oil and gas formations. Elevations 1960/1955 (G.L./K.B.)  
Conditions of Well - Good...

FORMATION	CONTENT	FROM	TO	SIZE	PULL IN	PULL OUT
	Surface Casing	0'	254'	8 5/8"	254'	0'
	Production Casing	0'	3242'	4 1/2"	3231'	1975'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Set C.T.B.P. at 2850'. Dumped 2 sx. Cement. Shot the 4 1/2" casing off at 1975'. Pulled 30 jts of 4 1/2", pumped 1st plug 50sx. Cement w/ 8 sx. Gel. Pulled 13 more jts and pumped 2nd Plug w/ 50sx Cement. Pulled last 49 jts. and pumped cement to surface.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address P.O. Box 847 Pratt Well Service Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Earl M. Knighton Jr. - Knighton Oil Co.

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart / Office Mng. P.W.S. INC. (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) P.O. Box 847, Pratt KS 67124

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 30 2000

SUBSCRIBED AND SWORN TO before me this 26 day of October, 2000

CONSERVATION DIVISION  
 Wichita, Kansas

Amy S. Robertson  
 Notary Public

My Commission Expires: 3/13/04

AMY S. ROBERTSON  
 Notary Public - State of Kansas  
 My Appt. Expires 3/13/04

15-151-20831-0000

# BIG SPRINGS DRILLING, INC.

P.O. BOX 8287  
MUNGER STATION  
WICHITA, KANSAS 67208

SUITE 29 • 400 NORTH WOODLAWN • (316) 681-1732

December 17, 1980

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 16 2000

## DRILLERS LOG

CONSERVATION DIVISION  
WICHITA, KS

Re: Healy #1  
C NW NW  
Sec. 20 Twp. 28S Rg 13W  
Pratt County, Kansas

OPERATOR: Earl M. Knighton  
CONTRACTOR: Big Springs Drilling, Inc.  
COMMENCED: December 9, 1980  
COMPLETED: December 14, 1980

Surface Pipe: Set 254' of 8 5/8" w/175 SX Common 2% gel 3% ccl

0	254'	Sand, Clay & Shale
254'	1927'	Shale
1927'	3085'	Lime & Shale
3085'	3242'	Lime
3242'		RTD


We certify that the above and foregoing is a true and correct copy of the log on the Healy #1 located in Pratt County, Kansas.


Big Springs Drilling, Inc.

  
Paul A. Seymour, Jr.

Subscribed and sworn to before me this 17th day of December, 1980.

My Commission Expires  
May 30, 1983

  
RUTH M. BASSETT  
STATE NOTARY PUBLIC  
Sedgewick County, Kansas  
My Appt. Exp. \_\_\_\_\_

  
Ruth M. Bassett Notary Public