


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027Wichita, Kansas 67217
NORTHLocate well correctly on above
Section Plat

WELL PLUGGING RECORD

Harper County, Sec. 35 Twp. 31 Rge. 9 W (E) (W)
 Location as "NE/CNW/SW" or footage from lines NE NE NE
 Lease Owner SeRoBee Drlg. Co., Inc. & Shaffer Oil Co.
 Lease Name Newberry Well No. 2
 Office Address 256 N. Topeka, Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole) Gas
 Date well completed September 1, 1973
 Application for plugging filed February 19, 1975
 Application for plugging approved February 21, 1975
 Plugging commenced February 21, 1975
 Plugging completed February 27, 1975
 Reason for abandonment of well or producing formation Not Productive
 If a producing well is abandoned, date of last production February 18, 1975
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4,433 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	218	None
				5 1/2	4,427	36.60

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand from 4,433 to 4,400'

5 sacks of cement from 4,400 to 4,370'

Ripped pipe at 3,800' and 3,660'

Wood bridge at 200'

Rock from 200' to 190'

30 sacks cement from 190' to 100'

Mud from 100' to 40'

Rock from 40' to 30'

10 sacks cement from 30' to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 1975

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Clarke Corporation
 Address Box 187, Medicine Lodge, Kansas 67104
 (If additional description is necessary, use BACK of this sheet)

STATE OF Kansas COUNTY OF Barber ss.

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Edna P. Morgenstern
 Medicine Lodge, Kansas
 (Address)

Subscribed and sworn to before me this 5th day of March, 1975

My commission expires April 4, 1978

Notary Public.