


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Harper County. Sec. 36 Twp. 31 Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Mull Drilling Company, Inc.
Lease Name Campbell Well No. 2
Office Address 1625 Wichita Plaza Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) SWD well
Date well completed _____ 19____
Application for plugging filed 8-20 1965
Application for plugging approved _____ 19____
Plugging commenced 8-24 1965
Plugging completed 8-28 1965
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation perforations Depth to top 1111 Bottom 1160 Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	120	
				5 1/2"	1111	3176.40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8-24-65 - Moved in, cleaned out cellar, filled with sand to 3930'
dumped 5 sacks cement

8-25-65 - Rigged up, working pipe, shot at 3700' and 3600'

8-26-65 - Working pipe. Shot at 3500' and 3430'

8-27-65 - Plugging rock bridge at 200'. Dumped 10 sacks cement.
Mud to 120', rock bridge, dumped 15 sacks cement.

8-28-65 - Fill hole. Set rock bridge, cap with 10 sacks cement.
Clean and dope threads and collars.

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1965
09-01-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P.O. Box 221, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P.O. Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1965

My commission expires January 26, 1967

Carmen R. Cook
Carmen R. Cook Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company, etal
 705 Fourth Nat'l Bank Bldg.
 LOCATION: Wichita, Kansas
 Campbell #2
 SW SW NE 36-31S-9W
 CONTRACTOR: Harper County, Kansas
 PICKRELL DRILLING COMPANY
 Wichita, Kansas

Rotary Drilling Commenced 7/28/54
 Rotary Drilling Completed 8/12/54

15-077-00132-0000 **RECEIVED**
 STATE CORPORATION COMMISSION

CASING RECORD:

120' of 8 5/8" surface casing set with 150 sacks
 bulk cement circulated.
 143 Jts. of 5 1/2" 14 1/2 lbs casing set at 4441'
 cemented with 100 sacks.

SEP 9 1965
 CONSERVATION DIVISION
 Wichita, Kansas

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Sand	40	Circ. for samples at	4350
Shale, Red Rock	160	" " " "	4360
Shale	350	" " " "	4370
Red Bed & Shale	890	" " " "	4385
Salt Shale & Shells	1086	" " " "	4410
Anhydrite	1110	" " " "	4459
Shale & Shells	1505		
Shale & Lime	1700		
Lime	2105	Slope test at	2130 - 0° off
Shale & Lime	2270	" " "	4285 - 0° off
Lime & Shale	2445		
Lime	3508	S.L.M. at	2130 - O.K.
Lime & Shale	3645	S.L.M. at	4285 - O.K.
Lime	4459	RED	

The undersigned, G. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By G. W. Sebitts
 Attorney-in-Fact

STATE OF KANSAS, }
 COUNTY OF SEDGWICK } ss.:

On this 26th day of August, 19 54, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared G. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

Baruch L. Water
 Notary Public