


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County. Sec. 2 Twp. 31S Rge. (X) 10 (W)  
Location as "NE/CNW/SW" or footage from lines C NW SW  
Lease Owner Graves Drilling Co., Inc.  
Lease Name Wallace Well No. 1  
Office Address 505 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 15, 1968  
Application for plugging filed April 15, 1968  
Application for plugging approved April 15, 1968  
Plugging commenced April 15, 1968  
Plugging completed April 15, 1968  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4590 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	224'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded up with heavy mud to 240 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
505 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of April, 1968

My commission expires May 9, 1971  
Betty Brandt Notary Public.

15-067-20059-0000

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: April 6, 1968  
505 Union Center  
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: April 15, 1968  
505 Union Center  
Wichita, Kansas 67202

CASING RECORD: 9 Jts. 224' 8-5/8" LOCATION: Wallace No. 1  
cemented with 200 sacks C NW SW  
Section 2-31S-10W  
Barber County, Kansas

-----

0 - 140	Sand
140 - 224	Red bed
224 - 1065	Red bed & shale
1065 - 1391	Shale & shells
1391 - 1825	Shale & lime
1825 - 2202	Lime & shale
2202 - 2415	Lime
2415 - 3410	Lime & shale
3410 - 3440	Sand
3440 - 3630	Lime & shale with sand
3630 - 3660	Shale
3660 - 3791	Sand & shale
3791 - 3805	Brown lime
3805 - 3980	Lime
3980 - 4090	Lime & shale
4090 - 4362	Lime
4362 - 4425	Lime & shale
4425 - 4530	Lime
4530 - 4590	Chert & lime
4590	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves  
President

STATE OF KANSAS )  
                  ) SS:  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 18th of April, 1968.

Betty Brandt  
Betty Brandt Notary Public

My commission expires: May 9, 1971