

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-007-20200-0000 Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Barber County. Sec. 3 Twp. 31S Rge. (X) 10 (W)
Location as "NE/CNW/SW" or footage from lines. C NW SE
Lease Owner John C. Graves-Mull Drilling
Lease Name Strong Well No. 1
Office Address 505 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 28, 19 72
Application for plugging filed February 28, 19 72
Application for plugging approved February 28, 19 72
Plugging commenced February 28, 19 72
Plugging completed February 28, 19 72
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. B. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4508 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 220 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of March, 19 72

My commission expires May 9, 1975
Betty Brandt Notary Public

15-007-20200-0000

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves-Mull Drilling DRILLING COMMENCED: February 15, 1972
505 Union Center
Wichita, Kansas 67218

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: February 28, 1972
505 Union Center
Wichita, Kansas 67202

CASING RECORD: 6 Jts. 261' 8-5/8"- cemented with 235 sacks
LOCATION: Strong No. 1
C NW SE
Section 3-31S-10W
Barber County, Kansas

0 - 261	Shale & sand
261 - 980	Red bed & shale
980 - 1810	Shale & shells
1810 - 2323	Lime & shale
2323 - 2490	Shale & lime
2490 - 2635	Shale with lime streaks
2635 - 3135	Shale & lime
3135 - 3693	Lime & shale
3693 - 3855	Shale & lime
3855 - 3990	Lime & shale
3990 - 4205	Lime
4205 - 4483	Lime & shale
4483 - 4490	Chert & dolomite
4490 - 4508	Chert
4508	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1972
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves
President

STATE OF KANSAS)
) ss.
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 8th day of March, 1972.

My commission expires: May 9, 1975.

Betty Brandt
Betty Brandt Notary Public