


15-077-20165-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Harper County, Sec. 26 Twp. 31 Rge. 9 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C SW SE  
Lease Owner Raymond Oil Co., Inc.  
Lease Name Jacobs #1 Well No.  
Office Address Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 8/20/77 19  
Plugging completed 8/25/77 19  
Reason for abandonment of well or producing formation  
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owen  
Producing formation Depth to top Bottom Total Depth of Well 4408  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	215	none
				5 1/2"	4398	3784

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Sanded hole to 4380' and set 5 sacks cement. Shot pipe at 3806', pulled 115 joints.  
Bailed hole to 230', set rock bridge and ran 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1977

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
WALTER VOHTS (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Walter Vohts  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 77


My commission expires



Margaret Melcher  
Notary Public.

DEC 29 1972

15-077-20165-0000



26-31-9W  
CSWSE

ROTARY DRILLERS' LOG

OPERATOR: SeRoBee Drilling Co.  
and Shaffer Oil Co.  
256 North Topeka  
Wichita, Kansas 67202

DRILLING COMMENCED: November 16, 1972

CONTRACTOR: Graves Drilling Co., Inc.  
505 Union Center  
Wichita, Kansas 67202

DRILLING COMPLETED: November 23, 1972

CASING RECORD: 10 Jts. 215' 8-5/8"  
cemented with 115 sacks.  
136 Jts. 4398' 5-1/2"  
cemented with 100 sacks.

LOCATION: Jacobs No. 1  
SW SE  
Section 26-31S-9W  
Harper County, Kansas

1602 KB

35 BopD

	0 - 240	Red bed
Smp Tops	240 - 1215	Red bed & shale
Lans	3652	
KC	3918	215 - 1366 Shale & shells
BKC	4196	
Miss	4396	1366 - 1785 Lime & shale
ID	4408	
	1785 - 2530	Shale & lime
	2530 - 3024	Lime & shale
	3024 - 3463	Lime
	3463 - 3555	Lime & shale
	3555 - 3573	Shale
	3573 - 3652	Sand & shale
	3652 - 3745	Lime
	3745 - 3815	Lime & shale
	3815 - 4285	Lime
	4285 - 4370	Lime & shale
	4370 - 4395	Shale
	4395 - 4408	Lime
	4408	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1977  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves  
President

STATE OF KANSAS )  
                          ) ss.  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 4th of December, 1972.

Betty Brandt  
Betty Brandt Notary Public

My commission expires:  
May 9, 1975