

15-191-19080-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

SUMNER County. Sec. 5 Twp. 34S Rge. 4 (W)

Location as "NE/CNW%SW%" or footage from lines SW NW NW

Lease Owner E. H. Adair, et al.

Lease Name NETAHLA Well No. 1.

Office Address 1019 East Second Street, Wichita 7, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry-hole.

Date well completed (With rotary) 4/24 19 57

Application for plugging filed 5/29 19 57

Application for plugging approved 5/29 19 57

Plugging commenced 5/29 19 57

Plugging completed 5/29 19 57

Reason for abandonment of well or producing formation \_\_\_\_\_

A dry-hole.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well W. G. Buffington, R.R. #2, Gauda Springs, Kansas.

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4733 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
(Driller's log attached hereto.)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped 5 sacks cement at 4708 feet on top of 25 feet of sand. Mud to 195 feet, 15 foot rock-bridge, 15 sacks cement at 180 feet. Mud to 40 feet, 10 foot rock-bridge, and 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair Oil Company

Address 1019 East Second Street, Wichita 7, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

K. W. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] K. W. Johnson

1019 E. Second St., Wichita 7, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 57.

My commission expires Sept. 15, 1957.

RECEIVED, Notary Public.  
STATE CORPORATION COMMISSION

JUN 11 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
E SEC 5 T34 R4W  
BOOK PAGE 16 LINE 10

15-191-19080-00.00

**E. H. ADAIR OIL COMPANY**  
**DRILLING CONTRACTORS**  
**PRODUCERS**  
1019 EAST SECOND STREET  
WICHITA 7, KANSAS

E.H.Adair Oil Co & A.F.Brann  
Netahla # 1  
SW NW NW 5-34-4W  
Sumner County, Kans.  
Elev. 1243 KB

Comm. 4-1-57  
Comp. 4-24-57  
Cont. Rig # 1  
8 5/8 @ 203' w/150 sx  
5 1/2 @ 4733 w/75 sax

Figures Indicate Bottoms of Formations

Shale & shells	203	shale	3900
Redbeds & shale	375	lime	3907
Shale & shells	1050	shale	3946
Shale & lime	1350	shaley lime	4138
Anhydrite & lime	1405	shale	4198
lime & shale	1657	lime	4206
lime	1825	shale	4306
lime & shale	2615	chert	4320
lime	2675	cherty lime and	
lime & shale	3149	cherty dolomite	4625
sand	3175	shale	4641
shale	3261	lime	4647
lime	3272	shale	4720
shaley sand	3296	black shale	4730
shale	3346	green sandy shale	4731
sand	3440	Sand, slight	
shale	3613	show oil	4733.
lime	3852	R.T.D.	4733

DD with cable tools  
to 4735. Shale from  
4733-35

tops:  
K.C. 3613  
Base K.C. 3852  
Miss 4306  
Kinderhook 4647  
Chattanooga 4720  
Simpson Shale 4730  
Simpson Sand 4731

Certified Correct.

*[Handwritten Signature]*

<b>PLUGGING</b>	
PL. SEC	5 T. 34 R. 4W
BOOK	PAGE 16 LINE 10

15-191-19080-00-00

E. H. Adair Oil Company  
 1019 East Second Street  
 Wichita 7, Kansas.

E. H. Adair, A. F. Brann, et al,  
 No. 1 Netahla  
 SW NW NW  
 Sec. 5-34-4 West  
 Sumner County, Kansas.

Comm.: 4-1-57  
 Comp.: 4-24-57  
 Contractor:  
 Adair - Rig No. 1  
 8-5/8 @ 203 feet w/ 150 sx.  
 5-1/2 @4733 feet w/ 75 sx.

Elevation 1243 K.B.

Figures indicate bottoms of Formations

Shale & shells	to 203	Shale	to 3900
Redbeds & shale	375	Lime	3907
Shale & shells	1050	Shale	3946
Shale & lime	1350	Shaley lime	4138
Anhydrite & lime	1405	Shale	4198
Lime & shale	1657	Lime	4206
Lime	1825	Shale	4306
Lime & shale	2615	Chert	4320
Lime	2675	Cherty lime &	
Lime & shale	3149	Cherty dolomite	4625
Sand	3175	Shale	4641
Shale	3261	Lime	4647
Lime	3272	Shale	4720
Shaley sand	3296	Black shale	4730
Shale	3346	Green sandy	
Sand	3440	shale	4731
Shale	3613	Sand, slight	
Lime	3852	show of oil	4733

	<u>Sample Tops</u>	<u>Electric-log tops</u>
LANSING	3261 (-2018)	
STALNAKER	3272 (-2029)	
KANSAS CITY	3613 (-2370)	3610 (-2367)
BASE K.C.	3852 (-2609)	3853 (-2610)
MISS. CHERT	4306 (-3063)	4311 (-3068)
MISS. LIME	4320 (-3077)	4318 (-3075)
BASE MISSISSIPPI	4625 (-3382)	4622 (-3379)
KINDERHOOK SHALE	4647 (-3404)	4645 (-3402)
CHATTANOOGA SHALE	4720 (-3477)	4719 (-3476)
SIMPSON SHALE	4730 (-3487)	
SIMPSON SAND	4731 (-3488)	

Certified correct:

*K. W. Johnson*  
 K. W. Johnson Geologist.

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 11 1957

CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 5 T. 34 R. 4W  
 BOOK PAGE 16 LINE 10