


15-191-01520-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kansas County. Sec. 5 Twp. 34S Rge. (X) 4 (W)
Location as "NE/CNW/SWK" or footage from lines SE NW SW NW
Lease Owner Time Petroleum Company
Lease Name Netahla Well No. 1
Office Address 512 Orpheum Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-20 19 55
Application for plugging filed 7-18-55 (Phone) 8-18- 19 55
Application for plugging approved 7-18-55 (Phone) 8-18 19 55
Plugging commenced 7-28 19 55
Plugging completed 7-30 19 55
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Buffington
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4720 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	202	none
				5 1/2	4707	4004

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud from 4720' to 210'
Filled with rock from 210' 200'
Filled with cement from 200' to 150'
Filled with mud from 150' to 35'
Filled with rock from 35' to 25'
Filled with cement from 25' to 0.
With cap welded on top of Surface pipe (10)".

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. W. Patterson & Son
Address Arkansas City, Kansas

STATE OF Kansas, COUNTY OF Sealquie, ss.
R. J. Schreiner (employed of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
512 Orpheum Bldg (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 1955
Barbara Oldfield

My commission expires October 29, 1956 Notary Public.

PLUGGING
FILE SEC 5 T34 R 4W
BOOK PAGE 143 LINE 19

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1955
11-30-55
CONSERVATION DIVISION
Wichita, Kansas

15-191-01520-00-00

Company: Time Petroleum Company
Farm: Netahla No. 1
Total Depth: 4707 1/2'
Comm. 6-20-55 Comp. 7-14-55
Shot or Treated:
Contractor: Kriswell Drilling Company
Issued:
Casing: 202" - 10 3/4" 4707" - 5 1/2"

Sec. 5, Twp. 34, Rge. 4W
Loc. SE 1/4 NW 1/4 NW 1/4
Sumner County, Kansas

Elevation:
Production:

FIGURES INDICATE BOTTOM OF FORMATIONS

- | | |
|------------------------------|-------------------------------|
| 100 - Soil, Clay and Red Bed | 3695 - Lime and Sandy Lime |
| 201 - Shale and Red Bed | 3717 - Lime |
| 300 - Red Bed and Shale | 3810 - Lime, Streaks of Shale |
| 810 - Shale and Shells | 3840 - Lime |
| 1180 - Lime and Shale | 3855 - Shale |
| 1250 - Lime | 3959 - Lime and Shale |
| 1330 - Shale | 4105 - Lime |
| 1345 - Shale and Lime | 4149 - Lime, Shale Streaks |
| 1480 - Lime | 4210 - Shale |
| 1575 - Lime and Shale | 4280 - Shale and Lime |
| 1980 - Shale and Lime | 4611 - Lime |
| 2010 - Sand and Shale | 4623 - Shale |
| 2190 - Shale and Lime | 4662 - Lime |
| 2280 - Shale | 4705 - Shale |
| 2380 - Sandy Shale | 4707 1/2 - Sand, T. D. |
| 2410 - Shale | |
| 2515 - Shale and Lime | |
| 2645 - Shale | |
| 2706 - Shale, Lime Streaks | |
| 3000 - Shale | |
| 3110 - Shale, Lime Streaks | |
| 3260 - Shale and Sand | |
| 3592 - Shale | |
| 3600 - Sandy Lime | |
| 3640 - Lime | |

I, J. S. Welfelt, of the Kriswell Drilling Company, certify the above rotary log to be true and correct.

KRISWELL DRILLING COMPANY

By J. S. Welfelt
J. S. Welfelt, Partner

PLUGGING
W. SEC 5 T34 R4E W
BOOK PAGE 143 LINE 19

RECEIVED
REGISTRATION COMMISSION
AUG 1 1955
REGISTRATION DIVISION
Wichita, Kansas