


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Sumner County, Sec. 5 Twp. 34 Rge. 4 W (X) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner H.C. Bennett  
Lease Name F. Nethala Well No. 1  
Office Address 1212 Union Nat'l Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed 5-11-55 \_\_\_\_\_ 19  
Application for plugging filed 3-10-67 \_\_\_\_\_ 19  
Application for plugging approved 3-13-67 \_\_\_\_\_ 19  
Plugging commenced 3-15-67 \_\_\_\_\_ 19  
Plugging completed 3-22-67 \_\_\_\_\_ 19  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Howard Hess  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4735 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	382	none
				5 1/2	4732	3800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mix and dump 4 sacks of cement at 4735

Globe Cementing Co. pumped 10 sacks of jell and 25 sacks of cement down surface pipe and stopped plug at 200'

Dump 5 sacks of Xjell and 10 sacks of cement from 200' to surface

RECEIVED  
STATE CORPORATION COMMISSION

MAR 31 1967

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Engineering and Const. Co.  
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

\_\_\_\_\_ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ronald R. Harrison

SUBSCRIBED AND SWORN to before me this 28 day of March, 1967

My commission expires Sept. 27, 1967

Ronald R. Harrison Notary Public.

15-191-01403-00-00


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

CONF

Company: SUNRAY OIL CORPORATION  
Farm: F. Nethala No. 1

SEC. 5 T. 34 R. 4W  
N. 1 SW NW

Total Depth. 4735  
Comm. 4-18-55 Comp. 5-11-55  
Shot or Treated.  
Contractor. Stickle Drilling Co.  
Issued. 8-6-55

County Sumner  
KANSAS  
  
Elevation. 1243 DF

CASING:  
8 5/8 382'  
5 1/2 4732' — 150 lbs cement

Production Pmp. 86.75 BOPD  
NW&G, fr. Simp. OH 4732-35

Figures indicate depth in feet

shale & shells	425
shale, salt & shells	805
anhydrite	860
lime & shale	925
shale & shells	1115
lime & shale	1290
lime	1410
lime & shale	1600
shale & shells	1860
shale & lime	2060
sandy shale & shells	2230
shale & lime	2415
shale & shells	2680
lime & shale	3110
shale & sandy lime	3212
shale & lime	3290
sand	3315
sandy shale & lime	3455
shale	3605
lime	3855
lime & shale	4123
shale	4305
lime	4377
lime & sand	4396
lime	4651
shale & lime	4684
shale	4729
sand	4735
Total Depth	

TOPS:

Kansas City	3618
Marmaton	3952
Cherokee	4140
Mississippi	4303
Kinderhook	4650
Chattanooga shale	4710
Simpson	4730

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1967  
CONSERVATION DIVISION  
Wichita, Kansas