



STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Summer County. Sec. 6 Twp. 34S Rge. 4W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NE NE
Lease Owner Time Petroleum Company
Lease Name Gerberding Well No. 1
Office Address 815 Union Nat'l Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) depleted-oil
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed April 8, 19 60
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie
Producing formation Depth to top Bottom Total Depth of Well 4718 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	REMOVED	PULLED OUT
					RECEIVED STATE CORPORATION COMMISSION APR 28 1966 CONSERVATION DIVISION Wichita, Kansas	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4712' 5 1/2" pipe set 100 sacks cement 245' 8 5/8" surface pipe set.
Cement circulated-hole filled with sand to 4700' and 5 sacks cement
at 230' set 20' rock bridge and 15 sacks cement mud to 35' set 5'
rock bridge and 10 sacks cement which filled hole to plow surface.
Recovered 4102' 5 1/2" pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Company
Address Box 364 Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgewick ss.
Employee of owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Max Sattentwate
815 Union National Bldg
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 26th day of April, 1966

My commission expires 8-6-69

Josephine Danner
Notary Public.

15-191-00604-00-00

69

TIME PETROLEUM COMPANY

GERBERDING NO. 1

SE NE NE Sec. 6-34S-4W
Sunder County, Kansas

Drilling started 6-21-54
Drilling completed 7-12-54
8 5/8" O.D. Casing Cemented @ 245'
5 1/2" O.D. Casing Cemented @ 4712'

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Remarks</u>
0	245		249' 8 5/8" O.D. Casing Cemented @ 245' with 175 sacks
245	665	Shale & Shells	
665	985	Anhydrite and Shale	
985	1350	Lime & Shale	
1350	1665	Lime	
1665	1835	Sandy Lime & Shale	
1835	2960	Lime & Shale	
2960	3040	Lime	
3040	3168	Lime and Shale	
3168	3248	Sand and Shale	
3248	3359	Sand & Lime	
3359	3476	Lime	
3476	3530	Sand & Lime	
3530	3624	Lime & Shale	
3624	3842	Lime	
3842	4107	Lime & Shale	
4107	4164	Lime	
4164	4296	Lime & Shale	
4296	4385	Lime	Top of Mississippi Lime - 4296'
4385	4405	Lime & Chert	
4405	4430	Lime	
4430	4445	Dolomite	
4445	4648	Lime	
4648	4711	Shale & Lime	
4711	4723	Sand	4127' 15 1/2" O.D. Casing set at 4712' with 100 sacks

This is a certified true copy of the Driller's Log as shown on the Daily Drilling Reports.

[Signature]
RADGER DRILLERS, INC.

Subscribed and sworn to before

me this 20th day of July, 1954

[Signature]
Notary Public

My Commission expires 10-20-57