

15-191-00625-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Sumner County. Sec. 11 Twp. 34 Rge. 4 (X) (W)

Location as "NE/CNW&SW" or footage from lines NW NW NE

Lease Owner Helmerich and Payne, Inc.

Lease Name Detrich Well No. 1

Office Address 1st Nat'l. Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/20 19 54

Application for plugging filed " 19 "

Application for plugging approved 7/20 19 "

Plugging commenced " 19 "

Plugging completed " 19 "

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. Buffington - Ark City, Kansas S. Plugger

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4782 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	195'	10 3/4"	195'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From	<u>4782</u>	to	<u>195'</u>	<u>Heavy rotary mud</u>
"	<u>195'</u>	"	<u>193 1/2'</u>	<u>Wooden plug</u>
"	<u>193 1/2'</u>	"	<u>165'</u>	<u>15 sacks cement - 1/2 sack hulls</u>
"	<u>165'</u>	"	<u>30'</u>	<u>Heavy rotary mud</u>
"	<u>30'</u>	"	<u>28 1/2'</u>	<u>Wooden plug</u>
"	<u>28 1/2'</u>	"	<u>9'</u>	<u>10 sacks cement - 1/2 sack hulls</u>
"	<u>9'</u>	"		<u>Rotary bushings to bottom of cellar</u>

FILED  
8-04-54  
COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.  
Address Box 88, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
T. W. Mahoney (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) T. W. Mahoney  
821 Central Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of August, 19 54

My commission expires Mar 30, 1957  
Rosemary Penrose Notary Public.

PLUGGING  
FILE SEC 11 T 34 R 4 W  
BOOK PAGE 50 LINE 12

DRILLER'S LOG

Company: Helmerich & Payne, Inc.

NW-NW-NE

Sec: 11, Twn: 34, Rge: 4

Farm: E. Detrick WellNo: 1

Total Depth: 4782'

County: Sumner,  
Kansas

Comm: 6/25/54 Comp: 7/20/54  
Contractor: Peel Brothers, Inc.

Elevation:

Casing: 10 3/4" @ 195' Cem.

Production: Dry hole

Figures below indicate bottom of formation

Clay and shale	0'	385'
Shale and shells		750
Shale and Anhydrite streaks		965
Shale and lime		1165
Shale		1200
Lime and shale		1500
Shale and shells		1560
Shale		2520
Lime		2680
Lime and shale		3565
Lime		3750
Lime and shale		3845
Lime		3860
Lime and shale		3905
Lime		4025
Lime and sandy shale		4095
Lime and shale		4295
Lime and chert		4311
Lime		4325
Lime and shale		4425
Lime		4465
Lime and shale		4475
Lime		4503
Lime and shale		4525
Lime		4640
Lime and shale		4737
Sand		4744
Lime and shale		4755
Lime		4772
Sand		4782
Total Depth		4782

This is to certify that the above information to the best of my knowledge is true and correct.

PEEL BROTHERS, INC.

BY *Harold E. Peel*

SUBSCRIBED AND SWORN TO before me this 3 day of August 1954

My commission expires September 28, 1954

Nov 30, 1957

*Rosemary Penrose*  
Notary Public

RECEIVED  
REGISTRATION COMMISSION  
AUG 4 - 1954  
REGISTRATION DIVISION  
Topeka, Kansas

PLUGGING  
FILE SEC 11 T 34 R 4W  
BOOK PAGE 50 LINE 12