

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Sumner County, Sec. 11 Twp. 34 Rge. 4 (E) 4 (W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner Iron Drilling Co
Lease Name Davis Well No. 1
Office Address Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-4-55 19
Application for plugging filed 11-4-55 19
Application for plugging approved 11-4-55 19
Plugging commenced 11-4-55 19
Plugging completed 11-4-55 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production Dry Hole 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4884 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Water	3549		8-5/8	274	None
Mississippi	"	4278				
Kinderhook	"	4604				
Misener	"	4667				
Simpson	"	4669				
Arbuckle	"	4849				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud - Set Bridging Plug @ 270'

Cemented w/ 20 sacks of Cement. Filled hole to 30 feet

Cemented w/ 15 sacks of Cement, filled hole to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. C. Patton
Address Wichita, Kans.



STATE OF Oklahoma, COUNTY OF Tulsa, ss.
J. L. Stackpole (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Iron Drilling Company
J. L. Stackpole (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 55

My commission expires Feb. 28, 1956

Notary Public.



15-191-00206-00-00

DRILLING RECORD

Well No. 1 Davis
SE NW SE 11-34-LW
Sumner County, Kans.

Casing Record

274" of 8-5/8" OD Surface Pipe
cemented with 200 sacks.

Work Began 10/9/55
Drilling Began 10/11/55
Drilling Completed 11/4/55
Work Completed 11/5/55

No Oil String - Dry Hole

Well Log

Soil & Clay	0 to 30
Sand	30 to 75
Red Bed, Shale & Shells	75 to 274
Shale & Shells	274 to 695
Lime & Shale	695 to 745
Shale & Shells	745 to 1100
Lime & Shale	1100 to 3555
K.C. Lime	3555 to 3566
Lime	3566 to 3910
Lime & Shale	3910 to 4253
Shale	4253 to 4278
Miss Lime Chert	4278 to 4288
Lime & Chert	4288 to 4496
Lime	4496 to 4523
Lime Chert	4523 to 4594
Lime	4594 to 4677
Lime & Shale	4677 to 4686
Shale & Sand	4686 to 4691
Sand	4691 to 4779
Sandy Shale	4779 to 4820
Lime	4820 to 4831
Lime & Shale	4831 to 4850
Lime & Chert	4850 to 4858
Arbuckle Lime	4858 to 4881
Lime	4881 to 4884 TD

PLUGGING

FILE SEC 11 T 34 R 4 W
BOOK PAGE 14 LINE 7

STATE OF KANSAS

NO. 22 1555

CONSERVATION DIVISION
Wichita, Kansas