

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-077-21427-00-00

LEASE NAME Zimmerman C

WELL NUMBER #2

990 Ft. from N Section Line

1320 Ft. from W Section Line

SEC. 25 TWP. 34S RGE. 8 (E) of (W)

COUNTY Harper

Date Well Completed \_\_\_\_\_

Plugging Commenced 9/24/2003

Plugging Completed 9/25/2003

RECEIVED  
OCT 01 2003

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Hartman Oil Company

ADDRESS 12950 E. 13th Street, Wichita, Ks 67230

PHONE# (620) 792-6776 OPERATORS LICENSE NO. 30535

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on September 23, 2003 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 4396' Bottom 5116' T.O. 5345'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	293'	8-5/8"	293'	0'
	Production	0'	5160'	5-1/2"	5160'	2/29.85'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Got to well and rigged up. Had Log-Tech on location. Set CIBP @ 4295'. Set jacks and pulled stretch into pipe-couldn't get slips out. Hauled torch down and heated head up. Got slips out. Run knife into 2730'-cut pipe. Pulled to 1350'-35sx; 850'-35sx & 325'-70 sx-circulated to surface. Tore jacks and rig down and moved off.

Name of Plugging Contractor D. S. & W. Well Servicing License No. 6901

Address P.O. Box 231, Claflin, Ks 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hartman Oil Company


STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, Ks 67525

SUBSCRIBED AND SWORN TO before me this 29th day of September, 2003

 KAREN J. MITCHELL  
Notary Public - State of Kansas  
My Appt. Expires 4/13/04  
My Commission Expires April 13th, 2006

Karen J. Mitchell  
Notary Public