

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 12 Twp. 28S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW

Lease Owner Imperial Oil Company

Lease Name KONOLD Well No. 1

Office Address 780 Fourth Natl Bldg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed June 20, 1962 19

Application for plugging filed June 20, 1962 19

Application for plugging approved June 20, 1962 19


Plugging commenced June 20, 1962 19

Plugging completed June 20, 1962 19

Reason for abandonment of well or producing formation
No commercial quantities of oil found

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Fred Hampel, Pretty Prairie

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4590 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	<u>Surface Casing 8-5/8"</u>	<u>736'</u>	<u>not pulled</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 500' with 20 sacks cement

Set top plug at 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address Box 97, WaKeeney, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John Lehman (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Lehman
780 Fourth Natl Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 62

Bette J. Behymer
Bette J. Behymer Notary Public.

My commission expires July 27, 1964

INVOICED

DATE 6/28/62

INV. NO. 5248-W

DRILLER'S LOG

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1962

CONSERVATION DIVISION
Wichita, Kansas

Imperial Oil Company
780 Fourth National Building
Wichita 2, Kansas

KONOLD NO. 1
NE SE SW Sec. 12-28S-13W
Pratt County, Kansas

Total Depth: 4590'

Elevation: 1883 K.B.
Production: Dry

Commenced: 6/5/62 Completed: 6/20/62

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" surface pipe at 730' with 375 sacks cement.

Figures indicate bottom of formations:

TOPS

Sand	120'	Wolfcampian Series	1989 (-106)
Shale & Shell	515'	Waubaunsee	2944 (-1061)
Sand	703'	Heebner	3615 (-1732)
Anhydrite & Shale	730'	Brown Lime	3799 (-1916)
Shale & Shell	2060'	Lansing	3819 (-1936)
Shale & Lime	2175'	B/Kansas City	4174 (-2291)
Shale & Shells	2525'	Mississippian	4269 (-2386)
Shale & Lime	3780'	Viola	4354 (-2471)
Lime	3867'	Simpson Shale	4422 (-2539)
Lime & Shale	3880'	Simpson Sand	4443 (-2560)
Lime	4340'	Arbuckle	4561 (-2678)
Lime & Chert	4475'	Rotary Total Depth	4590
Sand & Chert	4548'		
Lime & Chert	4590'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond R. Dombaugh
Raymond R. Dombaugh

Subscribed and sworn to before me this 26th day of June 1962.

My commission expires:

July 27, 1964

Bette J. Behymer
Bette J. Behymer, Notary Public