


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pratt County, Sec. 11 Twp. 28S Rge. (E) 13 (W)
Location as "NE/CNWxSWx" or footage from lines GSW/4SW/4
Lease Owner Amerada Petroleum Corporation
Lease Name Devlin Well No. 1
Office Address Box 197, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-9- 19 59
Application for plugging filed 12-9- 19 59
Application for plugging approved 12-9- 19 59
Plugging commenced 12-9- 19 59
Plugging completed 7:00 AM 12-9- 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4570 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	448'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton Spotted Plugs thru 4-1/2" DP as follows:
240' to 133' W/35 Sax Cement
45' to Top W/15 Sax Cement

REC'D
STATE CORPORATION COMMISSION
DEC 11 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Company
Address 1645 E. 21st - Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
Ernest Higgins (employee of owner) ~~and owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Higgins
Box 197, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 59

Charles W. Anderson
Notary Public.

My commission expires November 21, 1961



AMERADA PETROLEUM CORPORATION
 C SW/4 SW/4 Sec. 11-28S-13W
 Pratt, County, Kansas

DRILLER'S LOG:DEVLIN NO. 1

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Remarks</u>
0	30	Surface Clay	
30	140	Sand	
140	451	Red Bed	
451	1050	Red Bed & Shale	Ran 11 Jts. of 8-5/8"
1050	1680	Shale	casing, set at 448'
1680	1795	Shale & Shells	with 425 Sacks Cement
1795	1895	Shale & Lime	
1895	2420	Lime	
2420	2640	Lime & Shale	
2640	2800	Shale & Lime	
2800	2975	Shale	
2975	3065	Shale & Lime Streaks	
3065	3805	Lime & Shale	
3805	3850	Shale & Lime	
3850	4230	Lime	
4230	4385	Lime & Chert	
4385	4429	Cherty Lime	
4429	4456	Sand	
4456	4485	Sand & Chert	
4485	4500	Chert & Sand	
4500	4550	Shale & Sand	
4550	4570	Chert & Lime	
	4570	T.D. (Dry Hole)	

RECEIVED
 STATE CORPORATION COMMISSION

DEC 11 1959

CONSERVATION DIVISION
 Wichita, Kansas