


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 10 Twp. 28 Rge. 13 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines SE NE
Lease Owner Adair Oil Company
Lease Name Country Club #1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7/1/69 19
Plugging completed 7/3/69 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren
Producing formation Depth to top Bottom Total Depth of Well 4000 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				30"x	28"x	XXXXX
				8-5/8	799	none
				5 1/2"	4000	3489

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 3870', set 3 sacks of cement.
Loaded hole with water, shot pipe at 3498', worked pipe loose
and pulled 110 joints. Mudded hole to 320', set rock bridge
to 290' and plugged with 4 1/2 yards ready mix. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1969
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor
Address

(If additional description is necessary, use BACK of this sheet)
KNIGHT CASING PULLING CO., INC.
CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 7th day of July, 1969

My commission expires

Notary Public.

ADAIR OIL COMPANY
P. O. Box 7011
Wichita, Kansas

Adair Oil Company &
Graves Drilling Company
Country Club #1 (Washdown)
SE-NE
Section 10-28-13W
Pratt County, Kansas
E1. 1906 K. B.

Comm: 6-13-69
Comp: 6-24-69
Contractor: Graves Drilling Company
4½ @ 4,000 w/100 SX
Pro: D & A

Figures indicate bottom of formations:

shale & lime	3300
lime	3590
shale	3600
lime	3633
shale	3640
lime	3670
shale	3814
lime	3820
shale	3835
lime	4190
shale & lime	4283
chert & lime	4330
shale	4337
lime & chert	4420
sand & dolomite	4490
shale	4540
dolomite	4577
RTD	4577

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1969
CONSERVATION DIVISION
Wichita, Kansas

Sherrill Compton
Sherrill Compton
Geologist