

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado De'by Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-20293-0000

LEASE NAME Richard Smith

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 16 TWP. 28 RGE. 13 (MMM(W))

COUNTY Pratt

Date Well Completed

Plugging Commenced 10-18-95

Plugging Completed 10-23-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mike's Testing & Salvage, Inc.

ADDRESS P.O. Box 209 Chase, Ks. 67524

PHONE (316) 938-2943 OPERATORS LICENSE NO. 31529

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|---------|--------|------------|
| | | | | 13-3/8" | 197' | none |
| | | | | 4-1/2" | 3014' | 2052' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set Sanded bottom to 3836' and 4 sacks cement. Shot pipe at 2200', & 2052'. Loose at 2052. Pulled to 930' and pumped 25 sacks gel & 300# hulls & 160 sacks 60/40 POS 6% gel. Pulled 10 joints out. Pulled rest of casing Ran in with 7-joints of tubing to tag. Topped off cement at 217', pumped 60 sacks 60/40 POS 6% gel. Pulled up to 60' and pumped 40 sacks cement 60/40 Pos-6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage Chase, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so (Signature)

NOV - 2 1995 (Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 1st day of November, 1995

 Notary Public

USE ONLY ONE SIDE OF EACH FORM

