

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 16 TWP. 28 S RGE. 13 W E/W
Location as in quarters or footage from lines:
NW SE NW

Lease Owner Robert A. Clark
 Lease Name Harris Well No. #1
 Office Address 630 R. H. Garvey Bldg. - Wichit, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas
 Date Well Completed 6-30-78
 Application for plugging filed 7-14-82
 Plugging commenced 8-9-82
 Plugging completed 8-13-82
 Reason for abandonment of well or producing formation Dry

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3,244

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10 3/4"	266	None
				8 5/8"	990	None
				4 1/2"	3220	2407

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pluggedback at 2,770.
 Sand from 2,770 to 2,680 to 2,525
 4 sacks from 2,525 to 2,500
 4 sacks hull - 25 sacks cement - 25 sacks jell - 1 hull
 125 sacks 50-50 POZ - 4% Jell - 3% C. C.

RECEIVED
 AUG 19 1982
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Olmo R. Margenstern (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Olmo R. Margenstern
 (Address) Medicine Lodge, Mo.

SUBSCRIBED AND SWORN TO before me this 16th day of August 19 82

Jessie Hamerton
 Notary Public.

My Commission expires: April 4, 1984

KANSAS DRILLERS LOG

COMPANY Zorger Oil Co.

SEC. 16 T. 28S R. 13W
LOC. C-NW SE NW

FARM Harris

NO. 1

COUNTY Pratt

ROTARY TOTAL DEPTH 3,250'

COMM. June 17, 1978

COMP. June 25, 1978

CONTRACTOR H-30, Inc.

ISSUED June 30, 1978

CASING

10 3/4" Set at 266' cemented w/225 sxs cement

8 5/8" Set at 970' cemented w/100 sxs cement

5 1/2"

4 1/2" Set at 3,220' cemented w/150 sxs cement

ELEVATION 1,935 K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale and Shells	335'
Shale	1,200'
Shale and Lime	1,517'
Shale and Shells	1,942'
Shale and Lime	2,181'
Lime and Shale	2,720'
Shale and Lime	2,781'
Lime and Shale	3,250'
Rotary Total Depth	3,250'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1982
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 30th day of June, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978