

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5447 EXPIRATION DATE 6-30-84

OPERATOR Cities Service Oil & Gas Corp. API NO. 15-129-20668

ADDRESS 3545 N.W. 58th Street COUNTY Morton

Oklahoma City, Oklahoma 73112 FIELD N. Winter

\*\* CONTACT PERSON Mr. Raymond Hui PROD. FORMATION

PHONE 405 949-4400

PURCHASER LEASE Worthington A

ADDRESS WELL NO. 3

DRILLING Earl F. Wakefield, Inc. WELL LOCATION C SW SW

CONTRACTOR 300 W. Douglas 660 Ft. from South Line and

ADDRESS Wichita, Kansas 67202 660 Ft. from West Line of

the SW (Qtr.) SEC 2 TWP 33S RGE 43 (W).

PLUGGING Daco, Inc. WELL PLAT (Office Use Only)

CONTRACTOR DRAWER 3010 KCC ✓

ADDRESS Borger, TX 79007 KGS ✓

TOTAL DEPTH 5000' PBTD SWD/REP

SPUD DATE 7-22-83 DATE COMPLETED 8-1-83 PLG. ✓

ELEV: GR 3584' DF KB

DRILLED WITH (CABLE) (ROTARY) (TOOLS).

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

	2		
x			

Amount of surface pipe set and cemented 1363' DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

AFFIDAVIT

Verlin Meier, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Verlin Meier - Prod Region Mgr.

(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 10th day of August, 1983

(NOTARY PUBLIC)

MY COMMISSION EXPIRES: July 12, 1984

\*\* The person who can be reached by phone regarding any questions concerning this information.

AUG 17 1983

SIDE TWO

OPERATOR Cities Service O&G Corp.

LEASE Worthington A

ACO-1 WELL HISTORY (W)

SEC. 2 TWP. 33 RGE. 43 (W)

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 3

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run.					
Soils, sand & red bed		0	943	Dresser's Electric Logs:	
Glorietta Sand		943	1093	Dual Induction - SFL	
Red Bed & sand		1093	1364	W/GR & Caliper,	
Red Bed & Shale		1364	1834	CNL-FDC w/GR & caliper	
Red Bed		1834	2300		
Lime & Shale		2300	5000		
TOTAL DEPTH			5000'		

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)							
Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	30"	21"		23'	2 yds Redi mix		
Surface	12-1/4"	8-5/8"	24#	1363	65/35 Pozmix	650	2% CaCl, 1/2# flocele
					Class "H"	125	3% CaCl, 1/4# flocele
NO PRODUCTION CSG. SET							

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Pecker set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated

Date of first production Dry Hole	Producing method (flowing, pumping, gas lift, etc.) P & A 8-1-83	Gravity
--------------------------------------	---	---------

Estimated Production -I.P.	Oil bbls.	Gas bbls.	Water % MCF	Gas-oil ratio bbls.	CFPS
----------------------------	-----------	-----------	-------------	---------------------	------

Disposition of gas (vented, used on lease or sold) Perforations