

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-025-10108-00-00

API NUMBER None

LEASE NAME K. C. Harper

WELL NUMBER 3

SPOT LOCATION (C-SW-NW) 1980' FNL & 660' FW

SEC. 11 TWP. 34S RGE. 21W (XXXXXX) W

COUNTY Clark

Date Well Completed 9-11-55

Plugging Commenced 9/21/84

Plugging Completed 9/22/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Union Oil Company of California
ADDRESS 2000 Classen Center South Building
Oklahoma City, Oklahoma 73106

PHONE # (405) 528-7601 OPERATORS LICENSE NO. 5168

Character of Well Dry Hole - Converted to Wtr. Inj. Well
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 - Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Morrow Depth to top 5423' bottom 5498' T.D. 5508', 5504' PB

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Dry	5423	5498'	16"	77'	None
				9-5/8"	584'	None
				5-1/2"	5508'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

"SEE REVERSE SIDE FOR PLUGGING SUMMARY"

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Good Well Service Company License No. _____
Address Woodward, Oklahoma

STATE OF Oklahoma COUNTY OF Oklahoma, ss.


I, J. D. Norman (employee of operator) ~~xxx~~
~~xxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.
(Signature) J. D. Norman
(Address) 2000 Classen Center So. Bldg.
Oklahoma City, Oklahoma 73106

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 1984

My Commission expires: June 10, 1987

[Signature]
Notary Public

STATE CORPORATION COMMISSION
RECEIVED
OCT 04 1984



PLUGGING SUMMARY

M. I. R. U. D.D. Unit. R.I.H. w/4-3/4" bit on 2-3/8" tbg. to 4943' P.O.O.H.
R.I.H. w/tbg. open ended to 5429', spotted 50 sk. cmt. plug from 5429' - 4954',
pulled up to 4954' & displaced hole w/9# 36 Vis plug mud. P.O.O.H. w/tbg. Perf'd.
5-1/2" csg. @ 930' w/4-way squeeze shot, pumped in 265 sks. cmt. & squeezed 5 1/2"
x 9-5/8" annulus to surface through perf's @ 930', leaving cmt. plug inside 5 1/2"
from 930' to surface. P.O.O.H. w/tbg. Cut csg. strings off 3' below ground level
& welded on steel name plate. Well P&A 9/22/84.

1000
1000

1000

1000
1000
1000

1000

1000

1000

1000

1000

1000

1000

1000

1000
1000
1000

1000

1000

1000

1000

1000