


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Clark County, Sec. 15 Twp. 34S Rge. 21 E/WX
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-SE-NW
1980' FNL & 1980' FWL
Lease Owner Union Oil Company of California
Lease Name J. C. Harper "G" Well No. 1
Office Address 2000 Classen Center So. Bldg,
Oklahoma City, Oklahoma 73106
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Gas
Date Well completed January 14, 19 60
Application for plugging filed November 25, 19 80
Application for plugging approved December 2, 19 80
Plugging commenced December 1, 19 80
Plugging completed December 8, 19 80



Locate well correctly on above
Section Plat

Reason for abandonment of well or producing formation
Depleted
If a producing well is abandoned, date of last production
March 19 75
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Marmaton & Morrow Depth to top 5057 Bottom 5602' Total Depth of Well 5656'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Gas	5352	5602	13-3/8"	506'	None
Marmaton	Dry	5057	5224	8-5/8"	2599'	None
				4-1/2"	5556'	3500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from Surface feet to 5656' feet for each plug set. (10-18-75 Set cmt. ret. @ 5348' & squeezed Morrow perf's. 5461-69 w/100 sx. cmt. @ 3000# Dumped 10 sx. cmt. on top of retainer. Perforated Marmaton 5063-68', 5117-26' & 5178-95'. Set Cmt. ret. @ 5100' & squeezed perf's. 5117-26 & 5178-95 w/100 sx. cmt. @ 1900#) 12-1-80 M.I.R.U. unit P.O.O.H. w/tbg. R.I.H. w/4 1/2" gauge ring to 5060'. Set cmt. ret. @ 5025', loaded csg. w/wtr. & press. to 500#, load tbg. & squeezed perf's. 5063-68' w/100 sx. Class "H" cmt. Pull out of ret. & dump 5' cmt. on top of retainer. Displace hole w/10 lb. 36 Vis. mud. Shot 4 1/2" off @ 3499' & pulled out of hole w/approx. 3500' 4 1/2" csg. Spot 50 sx. cmt. plug 2649-2549', 25 sx. cmt. plug 700'-60', Cut 13-3/8" & 8-5/8" csg. off 4' below ground level, Spotted 10 sx. cmt. plug 34' to 4'. Welded on steel plate, filled cellar, removed all surface equipment. Well plugged and abandoned 12-8-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lillard Casing Pullers - Woodward, Oklahoma

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
J. D. Norman (employee ~~XXXXXX~~) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. D. Norman Senior Clerk
2000 Classen Center South Building
Oklahoma City, Oklahoma 73106
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 1980

My commission expires August 22, 1982

Wanda J. Cooper Notary Public.
Wichita, Kansas

