

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-025-10126-00-00

API NUMBER None

LEASE NAME Harper, Melville A

WELL NUMBER 1

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 18 TWP. 34S RGE. 21 (N) or (W)

COUNTY Clark

Date Well Completed 3/13/61

Plugging Commenced 7/26/89

Plugging Completed 7/28/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by n/a (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, Is well log attached? -

Producing Formation Toronto Depth to Top 4264 Bottom 4270 T.D. 5492

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Toronto	Gas	4264	70	8 5/8	587	None
				4 1/2	5489	2116

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 4200' w/15' cmt on top. (4185') Pumped 50 sx cmt plug from 970' to 700'. Pumped 40 sx cmt plug from 600' to 500'. Set a 10 sx cmt plug from 40' to 4'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Reeves Casing, Inc. License No. 3093

Address P. O. Box 94204, Oklahoma City, OK 73142

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 89

Judith E. Sussell
Notary Public

My Commission Expires: March 29, 1992