


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Clark County, Sec. 21 Twp. 31 Rge. 21 (E) (W) X
Location as "NE/CNW%SW%" or footage from lines C N.E. N.W.
Lease Owner McAdams Drilling Co.
Lease Name Shupe "A" Well No. 1
Office Address P. O. Drawer 960, Bristow, Okla. 74010
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-10 19 58
Application for plugging filed 12-3-73 19 73
Application for plugging approved 12-4 19 73
Plugging commenced 1-3-7 19 74
Plugging completed 1-9 19 74
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 11-30 19 73
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation Cherokee Depth to top 5395 Bottom 5400 Total Depth of Well 5555 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1569	1200
				5 1/2	5553	4430

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 20 sks. of cement @ 5300
Pump 50 sks. of cement @ 590 to 510
Put 15 sks. of cement @ 30 to 0

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF OKLAHOMA, COUNTY OF CREEK, ss.

T. P. McADAMS, JR. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Drawer 960 - Bristow, Oklahoma 74010
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of January, 1974

My commission expires September 23, 1975

Notary Public.

15-025-10129-00-00

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company. SUNRAY MID-CONTINENT OIL CO.
Farm. R. S. Shupe "A" No. 1

SEC. 21 T. 34 R. 21W
C NE NW

Total Depth. 5555'
Comm. 8-18-58 Comp. 9-10-58
Shot or Treated.
Contractor. Stickle Drlg.
Issued. 12-3-60

County Clark
KANSAS



Elevation. 1781' RB

Production. Dry

CASING:

20" 78' cem w/300 sx.
8 5/8" 1569' cem w/100 sx.
5 1/2" 5553' cem w/110 sx.

Figures Indicate Bottom of Formations.

surface	0
sand & clay	80
shale & shells	1880
Anhydrite	1910
shale & lime	2085
lime & shale	3295
shale & lime	3575
lime & shale	3895
shale & lime streaks	4045
shale & lime	4430
lime & shale	4552
lime	5309
lime & shale	5380
sand	5398
shale & sand	5424
lime, shale & sand	5470
lime & shale	5524
lime	5555
Total Depth	

TOPS:

Lansing	4454
Marmaton	5059
Base Cherokee	5352
Morrow Shale	5384
Morrow Sand	5396
Mississippi	5521

Gas 809,000 CFG & 2 BWPH, 18/64" ck.

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1973
CONSERVATION DIVISION
Wichita, Kansas