

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 2 Twp. 28 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW C NW

Lease Owner Morgenstern & Specter

Lease Name Fitzsimmons 'B' Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 4-8-44 19

Application for plugging filed July 9, 1963 19

Application for plugging approved July 10, 1963 19


Plugging commenced August 22, 1963 19

Plugging completed August 26, 1963 19

Reason for abandonment of well or producing formation Failure to produce profitably

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving Hays, Kansas

Producing formation Lansing Lime Depth to top 3489 Bottom 3493 Total Depth of Well 3532' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	380 ft.	none
				5 1/2" OD	3493 ft.	2037.06 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged, back with sand to 3480- feet, dumped 5- sacks cement.
Mudded hole up to 270- feet, Set a ten foot rock-bridge.
Dumped 20- sacks cement, Mudded hole up to 40- feet, Set a rock-bridge, dumped ten sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 3 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Company No. 457

Address R. Rt. 4 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Morganstern & Specter

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of August, 1963

My commission expires

Feb. 29, 1964

Barbara Costney (Krug)
Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas


copy

Company - SKELLY OIL CO.
Farm - Fitzsimmons "B" No. 1.

SEC. 2 T. 28 R. 11 W
NW 1/4 NW 1/4
330' fr NE 330' fr WL NW 1/4

Total Depth. 3532'
Comm. 2-26-44 Comp. 4-8-44
Shot or Treated. 4-10-44 3000 Gals. Acid 3491-3532
Contractor. Ruso Drlg. Co.
Issued. 6-3-44 Rotary O-3499 SIM
Cable 3499-3532

County. Pratt
KANSAS



CASING:
8 5/8" 380' Cem.
5 1/2" 3493' Cem.

Elevation. _____

Production. Pot. 450 B.
No wtr

Figures Indicate Bottom of Formations.

surface soil, sand, shells 0-280
shale & shells 380
red bed 440
red bed & shale 825
shale 1100
salt & shale 1240
shale 1425
lime 1815
shale 1885
lime 2100
lime & shale 2205
shale 2430
shale & lime 2655
lime 2735
shale 2775
lime 2830
shale & lime 2955
lime 3315
shale & lime 3425
shale 3471
lime brown oolitic & xlyn 3476
shale dk 3491
lime gy & brwn foss. 3497
lime gy & brwn xlyn. 3501
Corr: 3501 SIM rot. table
equals 3499 SIM derr. floor
lime gy xlyn, no sat. or por. 3517
lime lgt brown xlyn 3522
lime gy & brown 3529
good porosity & saturation,
sft from 3525-29 - 400'
OIH in 1 1/2 hrs
lime gy & brown, good poro.
& saturation 3532
last 1' hd - 1000' OIH 3 hrs
Total Depth.

Top Lansing Lime 3489 SIM

Before acid 1000' OIH 3 hrs
After acid flowed 15 hrs on
private test, 450 BO, no wtr

3489-3495 por. & slightly sat.
3495-99 slightly por. & oil
stained
3517-22 sli. por. & oil stained
3522-32 good porosity & sat.

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1963

CONSERVATION DIVISION
Wichita, Kansas