


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 2 Twp. 28 Rge. 11 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NE NW
Lease Owner Morgenstern & Specter NE
Lease Name Fitzsimmons "B" Well No. 2
Office Address Russell, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 5-6-48 19____
Application for plugging filed 7-9-63 19____
Application for plugging approved 7-10-63 19____
Plugging commenced July 31, 1963 19____
Plugging completed August 6, 1963 19____
Reason for abandonment of well or producing formation
Failure to produce profitably
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving Pratt, Kansas
Producing formation Lansing Lime Depth to top 3493 Bottom 3514 Total Depth of Well 3535 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	400'	none
				5 1/2	3514'	2025'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 3500- feet, Dumped 5- sacks cement.
Pumped ten sack Mud and 80- sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1963

08-12-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Company No. 457
Address R.R. 4 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Morgenstern & Specter
Russell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 63

My commission expires

Dec 1, 1964

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SURVEY
412 Union National Bk. Bldg., Wichita, Kansas


Company - SKELLY OIL COMPANY
Farm - Fitzsimmons "B" No. 2A

SEC. 2 T. 28 R. 11W
NW NE NW
330' FHL (990' FHL NW $\frac{1}{4}$

Total Depth. 3535 $\frac{1}{2}$ '
Comm. 4-10-48 Comp. 5-6-48
Shot or Treated. Acidized
Contractor. Claude Wentworth Drilling Co.
Issued. 8-7-48

County. Pratt

KANSAS



Elevation. _____

Production. 96 BO & 5 BW

CASING:
8-5/8" 400' Cem. w/225 sx
5-1/2" 3514' Cem. w/300 sx

* Figures Indicate Bottom of Formations.

surface soil & clay	0-40
sand & gravel	120
red bed	390
red bed & shells	400
red bed & shells	780
shale & lime shells	1080
salt	1200
shale & lime shells	1445
lime brkn	1595
shale & lime	1810
lime	1850
lime brkn & shale	1960
lime & shale	2345
shale	2460
shale & lime shells	2520
lime & shale	2865
lime sdy	2890
lime & shale	3140
lime	3284
lime & shale	3350
sand	3420
shale & lime	3493
lime gy fossiliferous	3500
lime gy xln	3520
lime brwn & gy	3535 $\frac{1}{2}$
Total Depth	

Tops:
Heebner Shale 3278
Lansing Lime 3493

3520-3535 $\frac{1}{2}$ 400' OIH in 5 hours.

acid. w/2500 gallons 3514-3535 $\frac{1}{2}$ ' (5-7-48)

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1963

CONSERVATION DIVISION
Wichita, Kansas