

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Summer County, Sec. 10 Twp. 30 Rge. 11 (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE

Lease Owner Thomas E. Sullivan

Lease Name Graham Well No. 1

Office Address 302 Midland Bldg., Kansas City, Missouri

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-20-52 19

Application for plugging filed 4-29-52 19

Application for plugging approved 4-29-52 19

Plugging commenced 5-24-52 19

Plugging completed 5-24-52 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production Dry Hole 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington

Producing formation Depth to top Bottom Total Depth of Well 3897 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4" O.D.	323	
				5 1/2" O.D.	3895	3314'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lead plug set in 5 1/2 casing at 3890'. Mudded to 3325'.
Dumped 6 sacks cement then mudded from 3314' to 325'.
Set bridge and dumped 15 sacks cement. Mudded to 20'
of the top then cemented from 20' to surface.

RECEIVED
STATE CORPORATION COMMISSION
AUG - 8 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chas. Oakes
Address R.R., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Wm. Williams*

707 Bitting Bldg., Wichita, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 1952

Deward S. Greider
Notary Public.

My commission expires Jan. 31, 1953

PLUGGING
FILE SEC 10 T 30 R 1 W
BOOK PAGE 12 LINE 25

George F. Kirshner - Graham Well No. 1

SE SW SE Sec. 10-30-1W Sumner County, Kansas.

Elevation 1257 G.F.

Total Depth Rotary 3897'
(Cable)
Drilling Comm. 4-2-52
Drilling Comp. 4-20-52
Contractor H. M. Williams

Casing:
10 3/4" O.D. 323' 240 S Cem
5 1/2" " " 3895' 150 " "

Figures indicate Bottom of Formations:

Surface Clay	45	
Shale & Shells	265	
Anhydrite	275	
Shale & Shells	315	
Anhydrite	323	
Anhydrite & Shale	360	
Shale & Shells	585	
Red Bed	605	
Shale & Lime Shells	935	
Shale	1195	
Shale & Shells	1535	
Lime & Shale	2080	
Lime	2170	
Shale & Red Bed	2335	
Shale & Lime	2620	
Sand	2676	
Shale	2705	
Lime & Shale	2735	
Shale	2850	
Lime	3075	Top K C Lime 3000'
Shale Shale	3105	
Shale & Lime	3238	
Shale	3278	
Lime	3315	
Lime & Shale	3461	
Lime	3762	Drill Stem Test at 3540' 30 Ft Mud and 210' Salt Water.
Lime & Shale	3815	
Lime	3840	
Shale & Shells	3850	
Shale	3892	Top Simpson Sand 3892'
Simpson Sand	3897	
Total Depth Rotary	3897	

STATE OF KANSAS,)
COUNTY OF SEDGWICK.) SS

This is to certify that this is a true and correct copy of the
drillers log of the above well.

M. M. Elms

Subscribed and sworn to before me a Notary Public this 21st day of April, 1952

My commission expires:
Feb. 2, 1953.

R. P. Conway
Notary Public

PLUGGING
W&A SEC-60-T-30-R-10
BOOK PAGE 12 LINE 28

RECEIVED
STATE COMMISSION
JUN 2 - 1952
CONSERVATION DIVISION
Wichita, Kansas