


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-025-1040-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Clark County, Sec. 3 Twp. 34S Rge. (E) 21(W)  
Location as "NE/CNW&SWK" or footage from lines NW/NW  
Lease Owner Ashland Oil & Refining Company  
Lease Name J. C. Harper Well No. 9  
Office Address Box 18695, Oklahoma City, Oklahoma 73118  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 11-27 1954  
Application for plugging filed 5-24 1968  
Application for plugging approved 5-27 1968  
Plugging commenced 5-27-68 19  
Plugging completed 7-2 1968  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well E. Eyes  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	2341	832
				5 1/2	5495	3872

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 30 sack cement plug from 5000 to 5200 feet. Pumped hole full of mud. Shot casing from 4210 to 3835 feet. Pulled 121 joints of 5 1/2". Shot 8 5/8" from 1535 to 823 feet. Pulled 11 joints of 8 5/8" -- pumped 50 sack plug from 400 to 550 feet. Pulled rest of 8 5/8" casing -- total of 26 joints. Refilled hole with mud. Capped well with 20 sacks cement and had cap welded on top of surface.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 23 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Gayle E. Toland & Co.  
Address Box 94336, Oklahoma City, Oklahoma 73109

STATE OF Oklahoma COUNTY OF Oklahoma, ss.  
Sid Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sid Wilson

(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of July, 1968

My commission expires 6-8-69

Notary Public.



