

15-025-20325-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Clark SEC. 3 TWP34 S RGE.21 W E/W
 Location as in quarters or footage from lines:
1780 FNL - 660 FEL

Lease Owner Texas Oil and Gas Corporation
 Lease Name Harper Ranch Well No. B-1
 Office Address Suite 300 - @00 W. Douglas - Wichita, Kansas 67201
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 11-17-79
 Application for plugging filed 10 - 82
 Plugging commenced 11-30-82
 Plugging completed 12-15-82
 Reason for abandonment of well or producing formation Dry

Locate Well
 correctly on above
 Section Plat.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 5550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	546	None
				4 1/2	5549	3598

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged back at 5,539
Sand from 5,539 to 5,400
4 sacks cement from 5,400 to 5,370
Pumped in 3 sacks hulls - 20 sacks jell - 70 sacks cement
15 sacks jell - 1 sack hull - 100 sacks cement - 50-50 POZ - 3% Jell - 3% C. C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Oliver R. Morgentern (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Medicine Lodge, Mo
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of Dec., 19 82

Jessie Hamilton
 Notary Public.

My Commission expires: April 4, 1986.

RECEIVED
 STATE CORPORATION COMMISSION

DEC 27 1982

CONSERVATION DIVISION
 Wichita Kansas

WELL LOG

HARPER RANCH "B" #1

15-025-20325-00-00

OPERATOR: TEXAS OIL & GAS
 CONTRACTOR: XPLOR DRILLING COMPANY

COMMENCED: 10/13/79
 COMPLETED: 10/26/79
 CASING RECORD: 8 5/8 @ 546'
 4 1/2 @ 5549'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Red Bed & Cement	70	745
Red Bed	745	1369
Shale	1369	2022
Shale & Lime	2022	5025
Lime	5025	5155
Shale & Lime	5155	5334
Lime	5334	5434
Core	5434	5477
Core, Shale & Sand	5477	5483
Core	5483	5502
Lime & Shale	5502	5550

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I certify that this is a true and correct copy of the Driller's Log on the well drilled 1780 FNL & 660 FEL, Sec. 3-34S-21W, Clark Co., Ks. to the best of my knowledge and belief.

XPLOR DRILLING COMPANY

Kirby C. Evers
 Kirby C. Evers, Vice President

RECEIVED
 STATE COMMISSION

Subscribed and sworn to before me this 30th day of October 1979.

OCT 18 1982

CONSERVATION DIVISION
 Wichita, Kansas

Mary Kay Ceding

MY COMMISSION EXPIRES: MY APPOINTMENT EXPIRES NOV 28, 1980