


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

15-025-10094-00-00



Locate well correctly on above Section Plat

Clark County, Sec. 4 Twp. 34 Rge. 21 (E) (W)

Location as "NE/CNW/SW" or footage from lines C-SW-NE-SW

Lease Owner George B. McClellan

Lease Name Harper Well No. 5

Office Address 19 East 11th St. P.O. Box 1216 Liberal, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 27, 1962 19

Application for plugging filed December 26, 1962 19

Application for plugging approved December 26, 1962 19

Plugging commenced December 27, 1962 19

Plugging completed December 27, 1962 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation None Depth to top Bottom Total Depth of Well 5550 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Top Soil & Sand	Dry	0	200			
Water Sand		200	485			
Anhydrite		485	590	8-5/8	583	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug set @ 1050'. Cemented with 35 sacks.

Top Plug set @ 40'. Plug consisted of one 8-5/8 rubber bridge plug. Cemented with 15 sacks and filled to ground level.

Plugging completed at 1:00 PM, December 27, 1962.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 3 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor McClellan Drilling, Inc.

Address 19 E. 11th St. P.O. Box 1216 Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
BILL CLIFFT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Clifft


Box 1216 Liberal, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1962

Sharon K. Halbrook Notary Public.

My commission expires Sept. 26, 1965

SHARON K. HALBROOK



15-025-10094-00-00

HARPER #5

George B. McClellan  
C-SW-NE-SW Section 4-34-21  
Clark County, Kansas

CASING RECORD:

Commenced: 12-12-62  
Completed: 12-27-62

Surface Pipe, run 19 jts. of 8-5/8"  
2 1/2". Casing set @ 581.17. Cemented  
bottom with 300 sacks with 2% CC.  
Basket set @ 150'. Cemented top  
with 150 sacks.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Top Soil	0	100
Sand and Clay	100	279
Sand	279	550
Anhydrite	550	590
Red Bed	590	800
Shale	800	1540
Shale, Anhydrite and Streaks	1540	1990
Shale and Lime	1990	2145
Shale and Lime	2145	2350
Lime and Shale	2350	2450
Lime	2450	2485
Lime and Shale	2485	2895
Shale and Lime	2895	3005
Shale	3005	4651
Lime and Shale	4651	4905
Lime	4905	5155
Shale	5155	5220
Shale and Lime	5220	5305
Lime and Shale	5305	5385
Shale	5385	5426
Lime	5426	5550

TD

Dry Hole

Set bottom plug @ 650'. Cemented  
with 35 sacks. Top plug @ 40'.  
Cemented with 15 sacks. Job  
completed @ 1:00 PM, 12-27-62.

NOTARY PUBLIC  
STATE OF KANSAS

JAN 16 1963

STATE OF KANSAS )  
                          ) SS  
COUNTY OF STEWARD )

CONSERVATION DIVISION  
WASHITA, KANSAS

I Hereby affirm that the above and foregoing is a true and  
correct copy of the log of the Harper #5 well, located C-SW-NE-SW of  
Section 4-34-21, Clark County, Kansas.

GEORGE B. McCLELLAN

Bill Clifft  
Bill Clifft, Driller

Subscribed and sworn to before me a Notary Public this 15<sup>th</sup>  
day of January, 19 63.

Sharon L. Halbrook  
Sharon F. Halbrook, Notary  
Public

My Commission Expires:  
Sept. 26, 1965