

15-119-30002-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*JP*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pioneer Production Corporation  
Complete Address Box 2542, Amarillo, Texas  
Lease Name H.G. Adams Well No. 1  
Location NE/4 Sec. 21 Twp. 34 Rge. 29 (E) (W)  
County Meade Total Depth 3375'  
Abandoned Oil Well        Gas Well X Input Well        SWD Well X D & A X  
Other well as hereafter indicated None  
Plugging Contractor Sargents Casing Pulling Co.  
Address Box 506. Liberal, Kansas License No. 511  
Operation Completed: Hour 1:00PM Day 5 Month 8 Year 1970

The above well was plugged as follows:

7" to 1370' circulated w/ cement. 2 7/8" to 3370' cemented.  
Top perforations 3278' Plug bottom w/ 20 sacks cement  
Top of cement 3270' Pumped 20 sacks cement into Disposal formation.  
Mud to 800' Spotted 35 sacks cement 800' to 650'  
Mud 650' to 40' Plug, Halls & 10 sacks cement 40' to 0'.  
Company Pump        Pulled 740' of 2 7/8" Tubing.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8/10/70  
INV. NO. 2355-W

Signed: *Edward J. Lewis*  
Well Plugging Supervisor