

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 25 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Trigg Exploration Company

Complete Address 410 Woolworth Bldg., Boulder, Colorado 80302

Lease Name Adams Well No. 1-12

Location C NW Sec. 12 Twp. 34 Rge. 28 (E) (W)

County Meade Total Depth 3144'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 11:00AM Day 21 Month 1 Year 1974

The above well was plugged as follows:

8 5/8" to 538' circulated w/ cement. 5 1/2" to 3144' cemented.

Top perforations 2993' Plug bottom w/ 20 sacks cement

Top of cement 2850' Mud 2850' to 538'

Spotted 35 sacks cement 538' to 438' Mud 438' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2323' of 5 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 1/30/74

Signed: Edward J. Evers  
Well Plugging Supervisor

INV. NO. 8461-W