

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-189-20,532-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name CITIES SERVICE COMPANY

Complete Address P.O. Box 300, Cities Service Bldg., Tulsa, OK 74102

Lease Name ALBRIGHT "A" Well No. #1

Location C.S.W. NE Sec. 35 Twp. 34 Rge. 35 (East) (West)

County STEVENS Total Depth 6842'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor DACO, INC.

Address DRAWER 3010, BORGER, TX, 79007 License No. _____

Operation Completed: Hour: 7 p.m. Day: 11 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The 8 5/8" d.p. @ 1649' w/650 sq. alcolite w/2% C.C. & 1/2 lb/floral
followed w/200 sq. common w/3% C.C. & 1/4 lb. flaseal.
The 5 1/2" cemented @ 6839' w/250 sq. 50-50 Poz-mix w/2% gel
18% salt, 1/4 lb. flaseal. & 8/10 oz 1% CFR-2
PBTD IN THE 7 7/8" is @ 6781'
PBTD IN THE 5 1/2" is @ 6240'
BT Plug @ 6250' w/cast iron bridge plug followed by
1 sq. common cement (see over)

Amount of Surface Casing: 1649'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. Starbuck
Conservation Division Agent
orders by S. Durrant

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
RECEIVED
AUG 24 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 8-30-82

INV. NO. 981 W

2ND plug set @ 2840' w/70 St. Common.

3RD plug ← ← 1680' w/25 St. Common.

4TH plug ← ← 34" to 0' w/10 St. Common.

8^{5/8}" Pipe cut off 4' below the surface
& covered with a welded cap.

Cementing done by Halliburton,