

15-077-00165-0000

Form CP-3
Rev. 6-26-62

¹⁰
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name William Gruenerwald & Associates

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name Hibbard Well No. # 1

Location NW SW Sec. 23 Twp. 34 Rge. 9 (E) (W) W

County Harper Total Depth 5055'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: 121 West 9th, Liberal, Kansas License No. 511

Operation Completed: Hour 12:00PM Day 25th Month Nov. Year 1966

The Above well was plugged as follows:

238' of 8 5/8" surface pipe, cemented with 175 sacks. 4794' of 5 1/2" long
string, cemented with 150 sacks. Plug back T.D. 4700'. Top perferation
4586'. Pumped 20 sacks of cement on bottom, with the top of the cement
at 4450'. 3800' of 5 1/2" long string was recovered from the hole. Fluid
level in the hole was at 225', bridge plug and rock bridge from 225'
to 215', and 40 sacks of cement pumped at 215'. Hole was filled with
mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 11/29/66
INV. NO. 4338-W