

15-077-10149-0000

Form CP-3  
Rev. 6-26-62

*90*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

November 13, 1962

RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1962

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name V. W. McKneb

Complete Address: Box 808, Winfield, Kansas

Lease Name Welch Well No. #1

Location NW - NW Sec. 12 Twp. 34 Rge. 6 (E) (W) X

County Harper Total Depth 3822'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Kent Well Service

Address: El Dorado, Kansas License No. 304

Operation Completed: Hour 5:00PM Day 17 Month Nov. Year 1962

The Above well was plugged as follows: 3821' of 4 1/2" long string perforated  
at 3790' to 3797'. Pipe sanded to 3780' with three sacks of cement. 300'  
of 8 5/8" surface pipe circulated with 300 sacks of cement. Hole filled  
to 200' with mud, 10' rock bridge, 20 sacks of cement. Hole filled to 40'  
with mud, 10' rock bridge, 10 sacks of cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Herman J. Justice  
Well Plugging Supervisor

DATE 11/29/62

INV. NO. 6066-W