

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Clarke Corporation

Complete Address: 101 N. Walnut, Medicine Lodge, Kansas

Lease Name Schubach Well No. # 1

Location NE SW Sec. 15 Twp. 34 Rge. 11 (E) (W) W

County Barber Total Depth 4602'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation

Address: 101 N. Walnut, Medicine Lodge, Kansas License No.

Operation Completed: Hour 11:00AM Day 27th Month Oct. Year 1965

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cement circulated. 4601' of 4 1/2" long string,
cemented with 75 sacks. Plug back to 4595'. Top perferation 4582', Bottom
of the hole was sanded to 4575', and cemented with 3 sacks. 4150' of 4 1/2"
long string was recovered from the hole. Fluid in the hole was bailed
down to 240', bridge plug and rock bridge from 240' to 230', and cemented
with 25 sacks. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 11/9/65
INV. NO. 2146-W