

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN - 2 1979  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 007-20553-0000 (of this well)

Operator's Full Name North American Oil & Exploration

Complete Address 2410 W 10<sup>th</sup> St, St. Paul, Kans 67530

Lease Name Donovan Well No. 1

Location C-NE-SE- Sec. 1 Twp. 34 Rge. 13 (E) (W) X

County Barber Total Depth 4648

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Nicholas Casing Pulling

Address Box 373 Geneseo, Kan 67444 License No. 711

Operation Completed: Hour 11:45 Am. Day 29 Month 12 Year 1978

The above well was plugged as follows:

355'- 8 5/8" Casing - 5 1/2" Casing set @ 4634' - Prof @ 3730' squeezed  
w/ 150 sac Cement - Top prof. @ 3554' sand back to 3530'  
topped sand w/ 5 sac mixed Cement w/ dump bailer Pull  
2724' - 5 1/2" Casing - Allied mixed & pumped 5 sac bulk  
20 sac gel - release plug - mixed & pumped 125 sac 60/40  
permix Cement w/ 29 gel - 37 CC. to top of Casing - Shut  
in w/ 400# pressure

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-3-79

INV. NO. 8855-W

Signed: [Signature]  
Well Plugging Supervisor