



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Westmore Drlg Co

Complete Address Chapin Bldg Medicine Lodge, KS

Lease Name Donovan Well No. 1

Location SW/SW/SE Sec. 1 Twp. 34 Rge. 13 (E) (W)

County Barber Total Depth 4733

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 4:00 PM Day 6 Month 11 Year 1974

The above well was plugged as follows:

206 ft 8 5/8 surface cement circulated. 4733 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4635 ft. Sand to 4600 ft, 5 sacks
cement with bailer. Pulled 3900 ft 5 1/2. Set 10 ft rock bridge at
240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 11/11/74
INV. NO. 279-W