

11-29

To: 1 020194
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,770-0000

NW NW NW, SEC. 12, T 34 S, R 31 W/E

4950 feet from S section line

4920 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Young-Nall Well # 1

Operator: TXO Production Corporation
Name & Address: 1660 Lincoln Street, Suite 1800
Denver, CO 80264

County Seward 191.43

Well Total Depth 5890 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1568

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9:30 a.m. Day: 28 Month: 11 Year: 19 88

Plugging proposal received from Bob Sargent

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5889' PBTB 5880' Perfs at 3444-50' CIBP at 5690' DV tool @ 3606' w/175 sx

1st plug pump 25 sx cement with 1 sx hulls to bottom

2nd plug run 50 sx cement at 1600'

3rd plug pump 35 sx cement at 700-560'

4th plug pump 10 sx cement at 40-0'

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)
Conservation Division Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 29 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement with 1 sx hulls to bottom,

2nd plug ran 50 sx cement at 1600-1350',

3rd plug pumped 35 sx cement at 700-560',

4th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2612' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 12-12-88
INV. NO. 23310

Signed Glenn R. Barlow (TECHNICIAN)