

8-12

2-040775

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 207B  
Wichita, Kansas 67202

API NUMBER: 15-077-00094-0000

75' N C SW NW SECTION 12 TOWNSHIP 34 RANGE 6W  
*NE*

OPERATOR LICENSE # 30151 FEET FROM S SECTION LINE \_\_\_\_\_  
FEET FROM E SECTION LINE \_\_\_\_\_

OPERATOR EASON DRILLING COMPANY  
NAME & TWO WEST SECOND STREET  
ADDRESS TULSA, OK 74103

LEASE NAME: MATTINGLY #1  
COUNTY: HARPER  
WELL TOTAL DEPTH: 5157' *167.60*

PIPE: 4-1/2" @ 3819'

SURFACE CASING: 13-3/8" @ 412' RECEIVED  
KANSAS CORPORATION COMMISSION

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_ SEP 20 1994

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: KELSO CASING PULLING CONSERVATION DIVISION  
ADDRESS: CHASE KS LICENSE: 6050 WICHITA, KS

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: RICHARD  
COMPANY NAME: KELSO CASING PHONE: \_\_\_\_\_

WERE: PBTD 3810' PERFS 3769'-3777' - SAND TO 3700' &  
4 SX - 35 SX @ 1000' - 35 SX @ 650' - 35 SX @ 450' -  
CIRC 250'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART (  ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1045 DAY: 12 MONTH: 8 YEAR: 1994

ACTUAL PLUGGING REPORT:  
PERS COVERED W/SAND FROM 3810' TO 3700' & CAPPED WITH  
4 SX CMT - PIPE RECOVERED 2664' & PULLED TO 1000' & 35  
SX CMT SPOTTED - PIPE PULLED TO 650' & 35 SX CMT  
SPOTTED - PIPE PULLED TO 450' & 35 SX SPOTTED - PIPE  
PULLED TO 250' & CMT CIRC TO SURF - REMAINING PIPE  
PULLED AND CMT TOPPED OFF

REMARKS: HOWCO #64453 60/40 6% GEL

I DID OBSERVE THIS PLUGGING.

**INVOICED**

DATE 9-26-94

INV. NO. 41252

8-12

  
Steve Van Gieson (AGENT)

FORM CP-2/3  
REV. 3/90